

VILLAGE OF ROANOKE					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER	OM3-L	12X36	1	3.00	
OBJECT MARKER	OM3-R	12X36	2	6.00	
STOP	R1-1	30X30	60	375.00	
YIELD	R1-2	36X36X36	43	167.52	
ALL WAY (PLAQUE)	R1-3P	18X06	33	24.75	
SPEED LIMIT 15	R2-1	24X30	1	5.00	
SPEED LIMIT 25	R2-1	24X30	22	110.00	
NO RIGHT TURN	R3-1	24X24	1	4.00	
NO LEFT TURN	R3-2	24X24	1	4.00	
NO U TURN	R3-4	24X24	3	12.00	
DO NOT ENTER	R5-1	30X30	2	12.50	
NO TRUCKS (SYMBOL)	R5-2	24X24	2	8.00	
ONE WAY (LEFT)	R6-2L	18X24	1	3.00	
SCHOOL	S1-1	30X30	10	62.50	
SCHOOL PLAQUE	S4-3P	24X08	2	2.67	
SCHOOL SPEED LIMIT	S4-1100	24X48	7	56.00	
CURVE RIGHT	W1-2R	30X30	1	6.25	
ONE DIRECTION LARGE ARROW	W1-6	48X24	2	16.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	4	32.00	
STOP AHEAD SYMBOL	W3-1	30X30	2	12.50	
REDUCED SPEED LIMIT AHEAD 25	W3-5	36X36	1	9.00	
ADVISORY SPEED (PLAQUE) 15 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	5	31.25	
(ARROW) DEAD END	W14-1A	36X08	7	14.00	
DEAD END (ARROW)	W14-1A	36X08	7	14.00	
		<b>TOTAL</b>	<b>221</b>	<b>993.2</b>	<b>0.0</b>

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			221
Z0051398	REMOVE EXISTING SIGN POST	EACH			22
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	22	264
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			22
	ASSEMBLY FOR TELESCOPING POST,	EACH			35
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			175
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			17
X7350010	SIGN SUPPORT BRACKET	EACH			6

1. Incidental items. See special provisions.

VILLAGE OF SECOR					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
STOP	R1-1	30X30	32	200.00	
YIELD	R1-2	36X36X36	21	81.81	
SPEED LIMIT 30	R2-1	24X30	16	80.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	2	6.00	
REVERSE CURVE LEFT	W1-4L	30X30	1	6.25	
TWO DIRECTION LARGE ARROW	W1-7	48X24	2	16.00	
STOP AHEAD (SYMBOL)	W3-1	30X30	1	6.25	
REDUCED SPEED LIMIT AHEAD 30 MPH	W3-5	36X36	2	18.00	
GRADE CROSSING ADVANCED WARNING	W10-1	36 DIA	4	36.00	
NO OUTLET	W14-2	30X30	1	6.25	
TRUCK ENTRANCE	W16-1101	30X30	1	6.25	
		<b>TOTAL</b>	<b>83</b>	<b>462.8</b>	<b>0.0</b>

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			87
Z0051398	REMOVE EXISTING SIGN POST	EACH			5
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	5	60
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			5
	ASSEMBLY FOR TELESCOPING POST,	EACH			5
72900100	METAL POST, TY A	FOOT	12	0	0
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			23
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			59
X7350010	SIGN SUPPORT BRACKET	EACH			2

1. Incidental items. See special provisions.

VILLAGE OF SPRING BAY					
DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
STOP	R1-1	30X30	53	331.25	
ALL WAY (PLAQUE)	R1-3P	18X24	3	9.00	
SPEED LIMIT 25	R2-1	24X30	10	50.00	
DEAD END	W14-1	30X30	5	31.25	
		<b>TOTAL</b>	<b>71</b>	<b>421.5</b>	<b>0.0</b>

PAY ITEM NUMBER	DESCRIPTION	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH			71
Z0051398	REMOVE EXISTING SIGN POST	EACH			16
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0	0
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH			0
	ASSEMBLY FOR TELESCOPING POST,	EACH			0
72900100	METAL POST, TY A	FOOT	12	16	192
72900200	METAL POST, TY B	FOOT	12	0	0
	ASSEMBLY FOR METAL POST,	EACH			72
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0	0
	ASSEMBLY FOR WOOD POST,	EACH			1
X7350010	SIGN SUPPORT BRACKET	EACH			0

1. Incidental items. See special provisions.

DESIGNED - KK	REVISED - KK 01/30/2013
DRAWN - KK	REVISED -
CHECKED - BNI	REVISED -
DATE - 10/18/12	REVISED -

Woodford County  
Highway Department

Municipal Schedule

SCALE:	SHEET NO. 17 OF 18 SHEETS	STA. TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
				10-0006-00-SG	Woodford	18	17
						CONTRACT NO.: 89628	