

COUNTY	ROUTE	SECTION	SHT. NO.
ADAMS	FAS 1600	11-00078-02-BR	2

SUMMARY OF QUANTITIES
GENERAL NOTES HMA REQUIREMENTS

93598

SUMMARY OF QUANTITIES

TOTAL QUANTITY	UNIT	ITEM	SPECIAL PROVISION	CODE NUMBER
68	CU YD	EARTH EXCAVATION		20200100
148	CU YD	CHANNEL EXCAVATION		20300100
16	CU YD	FURNISHED EXCAVATION	*	20400800
20	POUND	TEMPORARY EROSION CONTROL SEEDING		28000250
75	TON	AGGREGATE SURFACE COURSE, TYPE B		40200800
100	GALLON	BITUMINOUS MATERIALS (PRIME COAT)	*	40600100
15	TON	LEVELING BINDER (MACHINE METHOD), N50	*	40600625
105	TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	*	40603310
150	TON	AGGREGATE SHOULDERS, TYPE B		48101200
5.60	CU YD	CONCRETE STRUCTURES	*	50300225
1,391	SQ FT	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	*	50400405
570	POUND	REINFORCEMENT BARS, EPOXY COATED		50600208
100	FOOT	STEEL RAILING, TYPE S1		50900205
1	EACH	NAME PLATES		51500100
98	FOOT	PIPE CULVERTS, CLASS D, TYPE 2 24"	*	54201089
155	SQ YD	WATERPROOFING MEMBRANE SYSTEM		58100200
50	FOOT	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS		63000001
4	EACH	TRAFFIC BARRIER TERMINAL, TYPE 5A		63100075
4	EACH	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		63100167
300	FOOT	GUARDRAIL REMOVAL	*	63200310
1	L SUM	MOBILIZATION		67100100
40	FOOT	SHORT TERM PAVEMENT MARKING	*	70300100
4	EACH	TERMINAL MARKER - DIRECT APPLIED		78201000
1,490	SQ FT	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	*	X0320047
360	TON	STONE RIPRAP, CLASS A4 (SPECIAL)	*	X2810208
107	SQ YD	BRIDGE APPROACH PAVEMENT (SPECIAL)	*	X4201400
428	SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	*	X4401128
1	L SUM	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	*	X7010216

CONSTRUCTION TYPE CODE: 0014

△ SPECIALTY ITEMS

GENERAL NOTES

- SEEDING BY ADAMS COUNTY.
- PAVEMENT MARKINGS BY ADAMS COUNTY.

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

ITEM	AGG. COMPOSITION	ASPHALT GRADE	VOIDS
LEVELING BINDER	IL-9.5	PG 64-22	4.0% @ N50
HOT-MIX ASPHALT SURFACE COURSE	IL-9.5 OR IL-12.5 MIXTURE "C"	PG 64-22	4.0% @ N50

NOTE: HOT-MIX ASPHALT QUANTITIES CALCULATED @ 112#/SQ. YD./ IN.