

SUMMARY OF QUANTITIES					
CODE NO.	PAY ITEM	CONSTRUCTION CODE		0004	0011
		UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE
20200100	EARTH EXCAVATION	CU YD	136	136	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	20	
20300100	CHANNEL EXCAVATION	CU YD	717		717
* 21000300	GRANULAR EMBANKMENT, SPECIAL	TON	40	40	
* 21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	60	60	
25000200	SEEDING, CLASS 2	ACRE	0.6	0.6	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	54	54	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	54	54	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54	54	
25100115	MULCH, METHOD 2	ACRE	0.6	0.6	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60	60	
28000400	PERIMETER EROSION BARRIER	FOOT	618	618	
28000500	INLET AND PIPE PROTECTION	EACH	1	1	
28100107	STONE RIPRAP, CLASS A4	SQ YD	496		496
28200200	FILTER FABRIC	SQ YD	485		485
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	138	138	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	56	56	
44000100	PAVEMENT REMOVAL	SQ YD	140	140	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20	20	
48100100	AGGREGATE SHOULDERS, TYPE A	TON	110	110	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	82	82	
50200100	STRUCTURE EXCAVATION	CU YD	122		122
50200300	COFFERDAM EXCAVATION	CU YD	94		94
* 50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1
* 50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	103.5		103.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	123.9		123.9
50300260	BRIDGE DECK GROOVING	SQ YD	349	125	224
50300300	PROTECTIVE COAT	SQ YD	439	125	314
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	36,010		36,010
Δ 50901050	STEEL RAILING, TYPE SM	FOOT	164		164
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	746		746
51202305	DRIVING PILES	FOOT	746		746

\* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES					
CODE NO.	PAY ITEM	CONSTRUCTION CODE		0004	0011
		UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE
51203200	TEST PILE METAL SHELLS	EACH	2		2
51500100	NAME PLATES	EACH	1		1
54205491	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	166	166	
54215781	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	1	1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	32		32
Δ 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
Δ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	150	150	
67100100	MOBILIZATION	L SUM	1	1	
Δ 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	790	790	
Δ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
Δ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
* X0323265	REMOVE EXISTING RIPRAP	SQ YD	15	15	
* X2080250	TRENCH BACKFILL, SPECIAL	CU YD	9	9	
* X4201400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	125	125	
* X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	54		54
* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	98		98

\* SEE SPECIAL PROVISIONS Δ SPECIALTY ITEMS

FILE NAME = p:\m10320040\_macon county - oh 21 bridge replacement\plans\sheet\summary.dgn  
 PLOT DATE = 12/21/2012 10:49:31 AM

DESIGNED - R.L.H.	REVISED -
DRAWN - J.L.B.	REVISED -
CHECKED - S.M.W.	REVISED -
DATE - NOV. 2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE SHEET NO. 4 OF 25 SHEETS STA. TO STA.

F.A.S. RTE. 546	SECTION 10-00237-00-BR	COUNTY MACON	TOTAL SHEETS 25	SHEET NO. 4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 95694	