



**ROAD CLOSURE PLAN**

**TRAFFIC CONTROL NOTES**

1. TRAFFIC CONTROL AND PROTECTION SHALL BE IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION; THE APPLICABLE GUIDELINES CONTAINED IN THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS; STANDARDS 701301, 701901, BLR 21, AND BLR 22; THE TRAFFIC CONTROL PLANS; AND THE SPECIAL PROVISIONS.
2. TRAFFIC CONTROL AND PROTECTION DEVICES AND SIGNAGE WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR TRAFFIC CONTROL AND PROTECTION, SPECIAL. ALL ADDITIONAL TRAFFIC CONTROL DEVICES AND SIGNS REQUIRED FOR THE WORK AS SHOWN ON THE TRAFFIC CONTROL PLAN OR AS DIRECTED BY THE ENGINEER SHALL BE INCLUDED IN THE LUMP SUM PRICE OF TRAFFIC CONTROL AND PROTECTION, SPECIAL.
3. TRAFFIC CONTROL SURVEILLANCE WILL NOT BE PAID FOR SEPARATELY FOR THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSPECTING AND MAINTAINING ALL TRAFFIC CONTROL DEVICES AND SIGNS AT ALL TIMES INCLUDING NIGHTTIME, WEEKENDS, AND ANY TIME WORKERS ARE NOT PRESENT. THIS WORK SHALL BE PERFORMED IN ACCORDANCE WITH RECURRING SPECIAL PROVISION LRS3. THE COST OF ALL LABOR, MATERIALS, AND EQUIPMENT REQUIRED FOR THE INSPECTION AND MAINTENANCE OF THE TRAFFIC CONTROL DEVICES AND SIGNS SHALL BE INCLUDED IN THE LUMP SUM PRICE OF TRAFFIC CONTROL AND PROTECTION, SPECIAL.
4. FLASHING LIGHTS SHALL BE PLACED ON ALL TYPE III BARRICADES IN ACCORDANCE WITH STANDARD 701901 UNLESS OTHERWISE SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER.
5. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ALL ROAD CLOSURES A MINIMUM OF 48 HOURS IN ADVANCE OF THE ROAD CLOSURES.
6. MACON COUNTY WILL BE RESPONSIBLE FOR NOTIFYING THE PUBLIC, THE UNITED STATES POSTAL SERVICE, AND THE EMERGENCY SERVICE AGENCIES OF ALL ROAD CLOSURES.
7. THERE WILL BE A DEDUCTION FOR TRAFFIC CONTROL DEFICIENCIES AS SPECIFIED IN ARTICLE 105.03(b) OF THE STANDARD SPECIFICATIONS. CONTRACT UNIT PRICES SHALL NOT EXCEED 100% OF THE BID UNIT PRICE FOR TRAFFIC CONTROL AND PROTECTION, SPECIAL.

FILE NAME = p:\m0320040\_macon county - ch 21 bridge replacement\plans\sheet\traffo-control.dgn  
 PLOT DATE = 12/21/2012 10:49:37 AM

|                   |           |
|-------------------|-----------|
| DESIGNED - R.L.H. | REVISED - |
| DRAWN - J.L.B.    | REVISED - |
| CHECKED - S.M.W.  | REVISED - |
| DATE - NOV. 2012  | REVISED - |

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

**TRAFFIC CONTROL PLAN**

SCALE : NONE SHEET NO. 10 OF 25 SHEETS STA. TO STA.

| F.A.S. RTE.                                   | SECTION        | COUNTY | TOTAL SHEETS       | SHEET NO. |
|---|----------------|--------|--------------------|-----------|
| 546   | 10-00237-00-BR | MACON  | 25                 | 10        |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT |                |        | CONTRACT NO. 95694 |           |