April 23, 2013

SUBJECT: Central Illinois Regional Airport

Bloomington, Illinois McLean County

Illinois Project Number: BMI-4288

Contract No. BL069

Item No. 21A, April 26, 2013 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

Reason for Addendum:

Revising Plans and Specifications for additional quantity related to 9" PCC Pavement, Crushed Agg. Base Course – 6", Apron Light Pole w/ Triple Fixture, 4" Perforated Underdrain w/ Sock and Remove Underdrain.

Pay Item AR110011 - 1" Directional Bore, Contractor shall determine the size of the conduit needed to house the wires called out in note 3 of the Plan View Notes on the revised Apron Lighting Plan. The pay item description and number shall be as shown in the bid documents and as on plans, however the actual size of the bore needed may be greater than 1".

To All Plan Holders:

Schedule of Prices:

A revised Schedule of Prices is included in this addendum. Bidders must use the revised Schedule of Prices in preparing their bidding proposal. Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes into their computer programs.

Revisions to Plan Sheets:

Replace Plan Sheet 2 with Revised Plan Sheet 2A – Index to Sheets & Summary of Quantities.

- Quantities were revised to reflect changes that were made.

Replace Plan Sheet 4 with Revised Plan Sheet 4A - Construction Activity Plan.

 Location of Excess Excavation Stockpile has been relocated to the south side of the perimeter road.

Replace Plan Sheet 8 with Revised Plan Sheet 8A – Existing Conditions and Removals.

- Revised limits of pavement removal to show a portion of the perimeter road.

Replace Plan Sheet 10 with Revised Plan Sheet 10A - Existing Pavement Repair Plan.

- Added additional quantity for more panels to be replaced.

Replace Plan Sheet 11 with Revised Plan Sheet 11A - Proposed Improvements.

Revised limits of new 9" PCC pavement.

Replace Plan Sheet 17 with Revised Plan Sheet 17A - Jointing Plan 1.

Added Jointing for perimeter road.

Replace Plan Sheet 20 with Revised Plan Sheet 20A - Staking Plan.

 Added note stating that the pavement in the section will match the existing elevations.

Replace Plan Sheet 22 with Revised Plan Sheet 22A – Nose Tether Detail.

- Added note stating that steel shall be A36 U.N.O.

Replace Plan Sheet 24 with Revised Plan Sheet 24A - Drainage Improvements.

- Added note for additional underdrain to be placed.

Replace Plan Sheet 31 with Revised Plan Sheet 31A – Taxiway Lighting Plan.

Added location for directional bore and lights.

Replace Plan Sheet 35 with Revised Plan Sheet 35A - Apron Lighting Plan.

- Revised sheet for new lighting location and new wiring details.

Replace Plan Sheet 36 with Revised Plan Sheet 36A – Apron Lighting Details.

 Revised sheet for new 70' poles and additional requirements for obstruction light, Pin & Sleeve Receptacle and GFCI Receptacle.

Revisions to Specifications:

106-2.1 - Changes to 480V, LSI Hilton and 70' Poles.

106-2.2 - Pole certification to 90 MPH.

106-2.5 - Provide 5A fuses.

106-4.1 – Changes to 480V power, GFCI receptacle, Obstruction Lights and Pin & Sleve Receptacle.

106-5.2 - Delete Pay Item AR106503.

108-1.1 - HDPE Conduit.

108-2.2 - Deletion of the cable sizes.

108-4.3 – Revise what is called out to be paid for.

110-1.1 - HDPE Conduit.

125-2.14 - Remove reference to L-852D(L).

125-5.1 - Revise the pay item for MITL - Base Mounted in Shoulder to be AR125417.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Questions on this addendum may be directed to Chris Groth of Crawford, Murphy & Tilly at 217-787-8050.