



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 16, 2019

SUBJECT: FAI Route 74 (I-74)
Project NHPP-SCB2(239)
Section (10-7,8;92-8,9)RS-2(92-10)RS-3
Champaign & Vermilion Counties
Contract No. 70790
Item No. 90, April 26, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page iii of the Table of Contents to the Special Provisions.
2. Revised page 57 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief, Bureau of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

SEEDING FOR MEDIAN DRAINAGE REMEDIATION.....	54
STATUS OF UTILITIES	54
STRINGLINE	55
TEMPORARY RAMPS.....	55
TRAFFIC CONTROL SWITCHBACK.....	55
TREATMENT OF EXISTING FIELD TILE SYSTEMS	56
UNDERDRAIN CONNECTION TO STRUCTURE.....	57
WEED CONTROL MOWING STRIP (SPECIAL).....	58
MATERIAL TRANSFER DEVICE (BDE)	58
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	60
COMPENSABLE DELAY COSTS (BDE)	61
CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE).....	66
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	66
DISPOSAL FEES (BDE).....	76
EQUIPMENT PARKING AND STORAGE (BDE)	78
FUEL COST ADJUSTMENT (BDE)	78
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	82
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT PROJECTS) (BDE).....	86
HOT-MIX ASPHALT – OSCILLATORY ROLLER (BDE)	90
HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS -JOBSITE SAMPLING (BDE).....	92
HOT MIX ASPHALT – QUALITY CONTROL FOR PERFORMANCE (BDE).....	98
HOT-MIX ASPHALT – TACK COAT (BDE).....	104
LIGHTS ON BARRICADES (BDE).....	105
LUMINAIRES, LED (BDE)	106
MANHOLES, VALVE VAULTS, AND FLAT SLAB TOPS (BDE)	117

Method of Measurement. Couplers for pipe sizes smaller than 12 inches (300 mm) will not be measured separately for payment.

Concrete collars will be measured in cubic yards (cubic meters), not to exceed the dimensions shown in the plans.

Field tile junction vaults will be measured on an each basis.

Basis of Payment. Concrete collars will be paid for at the contract unit price per cubic yard (cubic meter) for MISCELLANEOUS CONCRETE, which price shall include all excavation and backfill.

The risers, gratings, and pipe tees for inspection wells shall be considered as included in the payment for STORM SEWER of the type and diameter specified.

Pay items not included in the contract and not included in other items of the contract will be paid according to Article 109.04 of the Standard Specifications.

UNDERDRAIN CONNECTION TO STRUCTURE

Pipe Underdrains 4" (Special) and Pipe Underdrains, Type 2, 6" shall be outletted to proposed or existing drainage structures as shown on the plans.

This work shall be done in accordance with the applicable portions of Section 601 and 602 of the Standard Specifications.

This work will be paid for at the contract unit price each for UNDERDRAIN CONNECTION TO STRUCTURE, which price shall be payment in full for connecting the underdrain to the structure.

Revised April 16, 2019