

SUMMARY OF QUANTITIES					ROADWAY	SAFETY	TRAINEES
S.P.	S.I.	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
						0004	0021 0042
		20200100	EARTH EXCAVATION	CU YD	2930	2930	
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	425	425	
		20800150	TRENCH BACKFILL	CU YD	100	100	
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1265	1265	
		21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1030	1030	
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3815	3815	
		21400100	GRADING AND SHAPING DITCHES	FOOT	200	200	
		25000210	SEEDING, CLASS 2A	ACRE	2.50	2.50	
		25000312	SEEDING, CLASS 4A	ACRE	0.50	0.50	
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	270	270	
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	270	270	
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	270	270	
		25100630	EROSION CONTROL BLANKET	SQ YD	13475	13475	
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300	
		28000305	TEMPORARY DITCH CHECKS	FOOT	420	420	
		28000400	PERIMETER EROSION BARRIER	FOOT	1775	1775	
		28100105	STONE RIPRAP, CLASS A3	SQ YD	60	60	
		28200200	FILTER FABRIC	SQ YD	60	60	
△		30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	425	425	
△		30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	8000	8000	8000
		31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3000		3000
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	25	25	
		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	165	165	
		35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	165	165	
		35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	615	615	
		35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	1050	1050	

SUMMARY OF QUANTITIES					ROADWAY	SAFETY	TRAINEES
S.P.	S.I.	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
						0004	0021 0042
		40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	30	30	
		40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	210	210	
		40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	7110	7110	
		40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	7315	7315	
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1165	1165	
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	425	425	
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	195	195	
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	200		200
		42400800	DETECTABLE WARNINGS	SQ FT	40		40
		44000100	PAVEMENT REMOVAL	SQ YD	2300	2300	
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	110	110	
		44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	25	25	
		44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	50	50	
		44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	50	50	
		44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	100	100	
		48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	870		870
		48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	800		800
		48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2210		2210
		50105220	PIPE CULVERT REMOVAL	FOOT	25	25	
△		54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	
△		54010403	PRECAST CONCRETE BOX CULVERTS 4' X 3'	FOOT	60	60	
		54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6	6	
△		542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	150	150	
△		60108204	PIPE UNDERDRAINS, TYPE 2, 4"	FOOT	3920	3920	
△	*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	750	750	

* - INDICATES SPECIALTY ITEMS
△ - INDICATES SPECIAL PROVISIONS

FILE NAME = 12450_02-QUAN-01 - IDOT-001	USER NAME =	DESIGNED -- WPD	REVISED -- Δ 4-15-19
		CHECKED -- PK	REVISED --
		DRAWN -- MED	REVISED --
		CHECKED -- APG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US ROUTE 52 AND GOUGAR ROAD INTERSECTION IMPROVEMENTS
SUMMARY OF QUANTITIES
SCALE: NONE SHEET NO. 3 OF 54 SHEETS STA. TO STA.

F.A.P. RTE. 0852	SECTION 13-00011-00-CH	COUNTY WILL	TOTAL SHEETS 54	SHEET NO. 3
CONTRACT NO. 61F88			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ---	