April 18, 2019

SUBJECT: Route FAU 1239 (Rockland Road)

Section 16-00116-00-PV

Lake County

Contract No. 61F75

Item 141

April 26, 2019 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised page 2 of the Index of Special Provisions
- 2. Revised page 61 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.

Bureau Chief

Engineer of Design and Environment

By: Ted B. Walschleger, P.E.

Tette abulye A.E.

Engineer of Project Management

ADJUSTING WATER SERVICE LINES	48
CONNECTION TO EXISTING WATER MAIN (NON PRESSURE)	48
DUCTILE IRON WATER MAIN	49
WATER MAIN, DUCTILE IRON PIPE, CLASS 52, 12", DIRECTIONALLY DRILLED	51
DUCTILE IRON WATER MAIN FITTINGS	
WATER SERVICE CONNECTION (SHORT & LONG)	53
WATER MAIN REMOVAL	
REMOVE EXISTING WATER VALVE	
VALVE VAULT TO BE ABANDONED	
CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER (SPECIAL)	
DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED	
EXPLORATION TRENCH, SPECIAL	
DUST CONTROL WATERING	
TRAFFIC CONTROL AND PROTECTION (ARTERIALS)	
TRAFFIC CONTROL PLAN	
TEMPORARY INFORMATION SIGNING	
TEMPORARY TRAFFIC SIGNAL TIMING	
STORM SEWER 84"	
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING	
LR107-4	
IEPA NOI	
SWPPP	
LPC 663	106

- (c) Consultant shall provide monthly observation of traffic signal operations in the field.
- (d) Consultant shall provide on-site consultation and adjust timings as necessary for construction stage changes, temporary traffic signal phase changes, and any other conditions affecting timing and phasing, including lane closures, detours, and other construction activities.
- (e) Consultant shall make timing adjustments and prepare comment responses as directed by the Area Traffic Signal Operations Engineer.
- (f) Return original timing plan once construction is complete.

Basis of Payment.

The work shall be paid for at the contract unit price each for TEMPORARY TRAFFIC SIGNAL TIMING, which price shall be payment in full for performing all work described herein per intersection. When the temporary traffic signal installation is turned on and/or detour implemented, 50 percent of the bid price will be paid. The remaining 50 percent of the bid price will be paid following the removal of the temporary traffic signal installation and/or detour.

STORM SEWER 84"

Description. This work consists of constructing storm sewer of the specified diameter per the applicable portions of Section 550 of the Standard Specifications except where modified herein. This work shall include the construction of pipe tee risers for connection to inlet structures.

The pipe tee shall be reinforced concrete and shall be fabricated according to Article 1042.06.

Method of Measurement. Storm sewers will be measured for payment in feet. When the storm sewer enters a manhole, inlet, or catch basin. Allowance will be made for the length of pipe necessary to permit the pipe to meet the sides of the manhole. No payment for storm sewer will be made through an inlet or manhole where the inlet or manhole is paid for as a separate item.

Trench backfill will be measured for payment according to Article 208.03

Excavation in rock will be measured for payment according to Article 502.12

Basis of Payment. This work will be paid for at the contract unit price per for STORM SEWER, of the class and type specified, 84".

Trench backfill will be paid for according to Article 208.04.

Excavation in rock will be paid for according to Article 502.13

Removal and replacement of unsuitable material below plan bedding grade will be paid for according to Article 109.04.