



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2019

SUBJECT: Route MUN 3073 (Woodfield Road)
Section 14-00114-02-PV (Schaumburg)
Cook County
Contract No. 61F10
Item 160
April 26, 2019 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 3-10 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Bureau Chief
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

MAINTENANCE OF ROADWAYS

Effective: September 30, 1985 Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the "Standard Specifications".

STATUS OF UTILITIES (D-1)

Effective: June 1, 2016

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information in regard to their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

UTILITIES TO BE ADJUSTED

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances resolution will be a function of the construction staging. The responsible agency must relocate or complete new installations as noted in the action column; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

Pre-Stage

STAGE/ LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	ACTION
Woodfield Road – Sta. 100+77, 63' LT	Underground duct	Existing underground duct in conflict with proposed storm sewer	AT&T	AT&T to relocate lines and install support <u>32</u> days
Woodfield Road – Sta. 106+16, 63' RT	Underground clay duct	Existing underground duct to be supported for proposed storm sewer installation	AT&T	
Woodfield Road – Sta. 108+80, 45' LT	Underground duct	Existing underground duct in conflict with proposed catch basin	AT&T	
Woodfield Road - Sta. 110+00, LT	Transformer	Existing transformer is in conflict with proposed pavement and curb and gutter.	ComEd	ComEd to relocate transformer and cable <u>15</u> days
Woodfield Road – Sta. 117+00, RT – Sta. 119+00, RT	Underground electric	Existing underground cable in conflict with proposed catch basins	ComEd	
NE corner of Woodfield Road/Meacham Road intersection	Underground Fiber Optic	Existing fiber optic line is in conflict with proposed catch basin	MCI/Verizon	MCI/Verizon to relocate lines and handholes <u>30</u> days
Woodfield Road - STA. 116+15.00, 39' RT	Underground Fiber Optic	Existing fiber optic line is in conflict with proposed fire hydrant	MCI/Verizon	
SW corner of Woodfield Road/Mall Drive intersection - STA. 116+62.75, 41' RT	Handhole	Existing MCI handhole is in conflict with proposed ADA ramp	MCI/Verizon	
Woodfield Road Sta. 101+00 to 122+50	Underground gas main	Multiple conflicts with proposed drainage, signals, and lighting structures.	Nicor	Nicor to relocate line <u>60</u> days

Pre-Stage: 32 Days Total Installation for AT&T
Pre-Stage: 15 Days Total Installation for ComEd
Pre-Stage: 30 Days Total Installation for MCI/XO
Pre-Stage: 60 Days Total Installation for Nicor
Pre-Stage Total: 137 Days Total

Stage 1

STAGE/ LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	ACTION
Woodfield Road – Sta. 101+40, 46' RT	Adjust during construction	Adjust manhole to proposed grade	MCI/Verizon	MCI/Verizon to adjust <u>1</u> day
Woodfield Road – Sta. 104+50, 58' RT	Adjust during construction	Adjust handhole to proposed grade	WOW	WOW to adjust <u>1</u> day
Woodfield Road – Sta. 107+03, 69' RT	Adjust during construction	Adjust manhole to proposed grade	AT&T	AT&T to adjust <u>1</u> day
Woodfield Road – Sta. 112+00, 42' RT	Adjust during construction	Adjust handhole to proposed grade	Comcast	Comcast to adjust <u>1</u> day
Woodfield Road – Sta. 114+23, 40' RT	Adjust during construction	Adjust handhole to proposed grade	WOW	WOW to adjust <u>1</u> day
Woodfield Road – Sta. 114+68, 52' RT	Adjust during construction	Adjust handhole to proposed grade	WOW	WOW to adjust <u>1</u> day
Woodfield Road – Sta. 116+30, 52' RT	Adjust during construction	Adjust manhole to proposed grade	AT&T	AT&T to adjust <u>1</u> day

Woodfield Road – Sta. 116+53, 45' RT	Adjust during construction	Adjust handhole to proposed grade	MCI/Verizon	MCI/Verizon to adjust <u>1</u> day
Woodfield Road – Sta. 119+85, 34' RT	Underground Electric to be shifted during construction	ComEd to shift cable out of the way of proposed catch basin installation	ComEd	ComEd to shift line <u>2</u> days
Woodfield Road – Sta. 121+00, 34' RT	Underground Electric to be shifted during construction	ComEd to shift cable out of the way of proposed catch basin installation	ComEd	ComEd to shift line <u>2</u> days

Stage 1: 2 Days Total Installation for AT&T
Stage 1: 2 Days Total Installation for MCI/Verizon
Stage 1: 3 Days Total Installation for WOW
Stage 1: 1 Days Total Installation for Comcast
Stage 1: 4 Days Total Installation for ComEd
Stage 1 Total: 12 Days Total

Stage 2

STAGE/ LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	ACTION
Woodfield Road – Sta. 107+77, 46' LT	Adjust during construction	Adjust manhole to proposed grade	AT&T	AT&T to adjust <u>1</u> day
Woodfield Road – Sta. 112+17, 36' LT	Adjust during construction	Adjust handhole to proposed grade	ComEd	ComEd to adjust <u>1</u> day
Woodfield Road - Sta. 116+30, 63.5' LT	Adjust during construction	Adjust handhole to proposed grade	MCI/Verizon	MCI/Verizon to adjust <u>1</u> day
Woodfield Road – Sta. 118+04, 46' LT	Adjust during construction	Adjust manhole to proposed grade	Level 3 Communications (Centurylink)	Centurylink to adjust <u>5</u> days

Stage 2: 1 Day Total Installation for AT&T
Stage 2: 1 Day Total Installation for ComEd
Stage 2: 1 Day Total Installation for MCI/Verizon
Stage 2: 5 Days Total Installation for Level 3
Stage 2 Total: 8 Days Total

Stage 3

STAGE/ LOCATION	TYPE	DESCRIPTION	RESPONSIBLE AGENCY	ACTION
Woodfield Road - Sta. 99+40, 47' RT	Adjust during construction	Adjust handhole to proposed grade	AT&T	AT&T to adjust <u>1</u> day

Stage 3: 1 Day Total Installation for AT&T
Stage 3 Total: 1 Day Total

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Address	Phone	e-mail address
AT&T	Bruce Robbins	1000 Commerce Drive, Floor 1, Oak Brook, IL 60523	630.573.6471	br1831@att.com
Comcast	Thomas Munar	688 Industrial Drive, Elmhurst, IL 60126	224.229.5851	Thomas_Munar@ cable.comcast.net
ComEd	Christian Mukania	1 Lincoln Center, 6 th Floor, Oakbrook Terrace, IL 60181	630.437.2927	Christian.Mukania@ comed.com
Level 3 Communications (Centurylink)	Vincent Skau	1305 E. Algonquin Road, Arlington Heights, IL 60005	847.954.8212	Vince.skau@ centurylink.com
MCI / Verizon / XO	Mel Conn	1515 E. Woodfield Road, Schaumburg, IL 60173	847-706-2315	Mel.conn@verizon.com
NICOR	Bruce Koppang	1844 Ferry Road, Naperville, IL 60563	630.388.3046	bkoppan@ southernco.com

WOW	Jared Trombetta	1674 Frontenac Road, Naperville, IL 60563	630.486.9038	Jared.trombetta@wowinc.com
-----	-----------------	---	--------------	----------------------------

UTILITIES TO BE WATCHED AND PROTECTED

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owners part can be secured.

Stage 1

STAGE/ LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
Woodfield Road – 98+50 LT – 122+40 LT, 99+00 RT – 118+20 RT, Plaza Drive (RT side), Mall Drive (LT side)	Buried communication and fiber optic lines	Existing communication and fiber optic lines; exercise caution during excavation	AT&T	Contractor to call JULIE before excavation
Woodfield Road – 100+85 RT-116+75 RT, Mall Drive – (LT side)	Buried cable TV and communication lines	Existing cable TV line; exercise caution during excavation	Comcast	Contractor to call JULIE before excavation
Woodfield Road – 116+50 RT – 122+50 RT, Mall Drive (both sides)	Buried electric lines	Existing electric lines; exercise caution during excavation	ComEd	Contractor to call JULIE before excavation
Woodfield Road – Mall Drive (both sides)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Centurylink	Contractor to call JULIE before excavation
Woodfield Road – 98+50 RT-116+85 RT, Mall Drive – (LT side)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	WOW	Contractor to call JULIE before excavation

Stage 2

STAGE/ LOCATION	TYPE	DESCRIPTION	OWNER	ACTION
Woodfield Road – 99+00 RT – 118+20 RT, Plaza Drive (RT side)	Buried communication and fiber optic lines	Existing communication and fiber optic lines; exercise caution during excavation	AT&T	Contractor to call JULIE before excavation
Woodfield Road – 100+85 LT-106+05 LT Plaza Drive (LT side)	Buried cable TV and communication lines	Existing cable TV line; exercise caution during excavation	Comcast	Contractor to call JULIE before excavation
Woodfield Road – 99+40 LT – 122+50 LT, Plaza Drive (LT side)	Buried electric lines	Existing electric lines; exercise caution during excavation	ComEd	Contractor to call JULIE before excavation
Woodfield Road – 107+00 LT-118+00 LT Plaza Drive (RT side)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Centurylink	Contractor to call JULIE before excavation
Woodfield Road – 98+50 LT-122+50 LT Plaza Drive – (RT side)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Vinakom	Contractor to call JULIE before excavation
Woodfield Road – Within existing AT&T duct on north side of Woodfield Road	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Windstream KDL	Contractor to call JULIE before excavation
Woodfield Road – 104+70 LT-106+30 LT Plaza Drive – (LT side)	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	WOW	Contractor to call JULIE before excavation
Woodfield Road – Within existing AT&T duct on north side of Woodfield Road	Buried fiber optic lines	Existing fiber optic lines; exercise caution during excavation	Zayo	Contractor to call JULIE before excavation

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

Agency/Company Responsible to Resolve Conflict	Name of contact	Address	Phone	e-mail address
Vinakom	Dicky Patel	860 Remington Road, Schaumburg, IL 60173	847.592.5785	dicky.patel@vinakom.com
Windstream KDL	Deven Barnhill	3765 Lexington Drive, Hoffman Estates, IL 60192	847.345.4024	deven.barnhill@windstream.com
Zayo	John Ferraresi		312.216.0450	John.ferraresi@zayo.com

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be taken into account in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided in the action column for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation dates must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies. The Department's contractor is responsible for contacting J.U.L.I.E. prior to any and all excavation work.