

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0044				
20200100	EARTH EXCAVATION	CU YD	1596	1596				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	162	162				
25200110	SODDING, SALT TOLERANT	SO YD	162	162				
25200200	SUPPLEMENTAL WATERING	UNIT	21.7	21.7				
28000510	INLET FILTERS	EACH	5	5				
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SO YD	7181	7181				
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	15388	15388				
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	1539	1539				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1149	1149				
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	575	575				
42001300	PROTECTIVE COAT	SO YD	321	321				
42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SO YD	312	312				
44000100	PAVEMENT REMOVAL	SO YD	7181	7181				
44000300	CURB REMOVAL	FOOT	734	734				
* SPECIALTY ITEMS								

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0044				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	837	837				
66400505	CHAIN LINK FENCE, 8'	FOOT	135	135				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1480	1480				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	6	6				
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1	1				
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1				
* 66901005	ENGINEERING BARRIER	SQYD	1745	1745				
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	10	10				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
* 72000100	SIGN PANEL - TYPE 1	SO FT	2	2				
* 72900100	METAL POST - TYPE A	FOOT	11	11				

FILE NAME =	USER NAME = RanaKata	DESIGNED -	REVISED -
pw\N\dot-pw\benray.com\PW\DOT\Documents\100T		DRAWN -	REVISED -
Offices\District\Projects\DOT\B24\CADD\dot\Design\DOT\B24-sh-5		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**LANDSCAPE MAINTENANCE YARD (AUGUSTA BLVD)
SUMMARY OF QUANTITIES**

F.A. RTÉ.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2023 LS YARD PARKING	COOK	15	4
CONTRACT NO. 62W01				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

△ REVISED SHEET 4/3/2024