

LOCATION OF WORK: FAP 709 (US 136) MINOR ARTERIAL RURAL STA. 460+00 STA. 460+85 CHAMPAIGN 80% FED / 20% STATE 0004

FAP 709 (US 136) MINOR ARTERIAL RURAL STA. 545+00 STA. 545+95 CHAMPAIGN 80% FED / 20% STATE 0004

FUNDING BREAKOUT: 80% FED / 20% STATE

CONSTRUCTION TYPE CODE: 0004

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SN 010-8178	SN 010-8179
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.00		1.00
51500100	NAME PLATES	EACH	2.00	1.00	1.00
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	93.00	60.00	33.00
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2.00	2.00	
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2.00		2.00
54011203	PRECAST CONCRETE BOX CULVERTS 12' X 3'	FOOT	56.00	28.00	28.00
54248510	CONCRETE COLLAR	CU YD	1.00	0.50	0.50
54260315	TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTION	FOOT	211.00	105.50	105.50
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1.00		1.00
60500050	REMOVING CATCH BASINS	EACH	1.00		1.00
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	120.00	60.00	60.00
61140100	STORM SEWERS (SPECIAL), 10"	FOOT	15.00	15.00	
61140200	STORM SEWERS (SPECIAL), 12"	FOOT	45.00	15.00	30.00
63200310	GUARDRAIL REMOVAL	FOOT	635.0	0.0	635.0
67100100	MOBILIZATION	L SUM	1.00	0.50	0.50
* DENOTES SPECIALTY ITEM					

MODEL: SOQ-1 [Sheet]
FILE NAME: c:\p\work\p\work\p\personnel\0900796\0510753-shh-SOQ.dgn

USER NAME = Bridgette.Pierson	DESIGNED -	REVISED -
PLOT SCALE = 0.16666833' / in.	DRAWN -	REVISED -
PLOT DATE = 1/31/2024	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	113CR	CHAMPAIGN	42	4
CONTRACT NO. 70753				
ILLINOIS FED. AID PROJECT				