

80% FED
20% STATE

CONSTR. CODE

FAS 674

ROADWAY

0005

RURAL

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
63200310	GUARDRAIL REMOVAL	FOOT	3726	3726
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	28
70300100	SHORT TERM PAVEMENT MARKING	FOOT	12807	12807
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	4316	4316
70300211	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS - PAINT	SQ FT	81	81
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	24	24
70300221	TEMPORARY PAVEMENT MARKING - LINE 4" - PAINT	FOOT	120,764	120,764
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	81	81
70300251	TEMPORARY PAVEMENT MARKING - LINE 8" - PAINT	FOOT	146	146
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2311	2311
70300261	TEMPORARY PAVEMENT MARKING - LINE 12" - PAINT	FOOT	482	482
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	146	146
70300281	TEMPORARY PAVEMENT MARKING - LINE 24" - PAINT	FOOT	32	32

△
△
△
△
△
△
△
△
△

* SPECIALTY ITEM

△ REVISÉD 4-15-2024
△ REVISÉD 4-9-2024

REV. - MS

MODEL: Default
FILE NAME: I:\DDT\8636 D7 16r\16r\8636.02_W0 2 - Lake Paradise Road Resurfacing\CADD\CADD_Civil\071986-11t-500.dgn



USER NAME = switt	DESIGNED - HEK	REVISED -
PLOT SCALE = 0.167 / in.	DRAWN - HEK	REVISED -
PLOT DATE = 2/6/2024	CHECKED - CMF	REVISED -
	DATE - 10-05-2023	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
FAS 674 - IL 16 TO CUMBERLAND COUNTY LINE	
SCALE: _____	SHEET 3 OF 5 SHEETS STA. _____ TO STA. _____

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
674	D7 HMA RESURF 2024-1	COLES	48	5
CONTRACT NO. 74986				
ILLINOIS FED. AID PROJECT				

PAVEMENT MARKING SCHEDULE

STATION	TO	STATION	LENGTH	PAINT PAVEMENT MARKING - LINE 4"(WHITE) 78001110	PAINT PAVEMENT MARKING - LINE 4"(YELLOW SKIP DASH) 78001110	PAINT PAVEMENT MARKING - LINE 4"(YELLOW SOLID) 78001110	PAINT PAVEMENT MARKING - LINE 4"(YELLOW SOLID - DOUBLE) 78001110	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS 78000100	THERMOPLASTIC PAVEMENT MARKING - LINE 4" 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 8" 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 12" 78000600		THERMOPLASTIC PAVEMENT MARKING - LINE 24" 78000650	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS 78011000	GROOVING FOR RECESSED PAVEMENT MARKING 5" 78011025	GROOVING FOR RECESSED PAVEMENT MARKING 9" 78011045	GROOVING FOR RECESSED PAVEMENT MARKING 13" 78011065	GROOVING FOR RECESSED PAVEMENT MARKING 25" 78011125
				FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	(YELLOW) - FOOT	FOOT	(WHITE) - FOOT	(YELLOW) - FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT
10+31.50	TO	14+70.00	439	1043					1708	146	226	244	32		1708	146	482	32
14+70.00	TO	124+73.69	11004	21675	2513	1620	1700		400			12			400			
STA.124+73.69 BK = STA. 10+00.00 AH																		
10+00.00	TO	23+83.98	1384	2430	346	634		62	203					66	203			
23+83.98	TO	33+89.93	1006	1920			2012											
33+89.93	TO	39+59.75	570	1140			1140											
39+59.75	TO	49+26.76	967	1800			1934											
49+26.76	TO	56+00.00	673	1346			1346											
56+00.00	TO	116+66.47	6066	11891	1517	1900												
STA.116+66.47 BK = STA. 33+73.30 AH																		
33+73.30	TO	36+00.00	227	453	57	227												
36+00.00	TO	44+00.00	800	1600			1600											
44+00.00	TO	54+00.52	1001	1740			2001											
54+00.52	TO	96+00.06	4200	8064	1050	2940												
STA.96+00.006 BK = STA. 179+81.99 AH																		
100+35.00	TO	179+81.99	7947	15740	1987			18						23				
STA.100+35.00 BK = STA. 10+00.00 AH																		
10+00.00	TO	22+60.32	1260	2370	315	600												
22+60.32	TO	38+54.74	1594	3119			3189											
38+54.74	TO	54+56.01	1601	3203	400	420												
54+56.01	TO	69+72.11	1516	3032			3032											
69+72.11	TO	74+05.00	433	866	108	433												
			Total	83432	8293	8774	17954	81	2311	146	226	256	32	89	2311	146	482	32

2 REVISED SHEET 4-15-2024

MODEL: Default
FILE NAME: I:\DOT\8636 D7\ar\ar\8636\03 - W0 2 - Lake Paradise Road Resurfacing\CADD\CADD_CHMID71986s-ht-schedule.dgn



USER NAME = switt	DESIGNED - HEK	REVISED - _____
	DRAWN - HEK	REVISED - _____
PLOT SCALE = 0.167' / in.	CHECKED - CMF	REVISED - _____
PLOT DATE = 2/6/2024	DATE - 10-05-2023	REVISED - _____

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES	
FAS 674 - IL 16 TO CUMBERLAND COUNTY LINE	
SCALE: _____	SHEET 9 OF 10 SHEETS STA. _____ TO STA. _____

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
674	D7 HMA RESURF 2024-1	COLES	48	19
CONTRACT NO. 74986				
ILLINOIS FED. AID PROJECT				