

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	50
25000100	SEEDING, CLASS 1	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23
25100115	MULCH, METHOD 2	ACRE	0.25
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	131
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	9097
40600370	LONGITUDINAL JOINT SEALANT	FOOT	4907
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	112
40600990	TEMPORARY RAMP	SQ YD	92
40603215	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N50	TON	885
40604050	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N50	TON	1062
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1176

△

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
42400800	DETECTABLE WARNINGS	SQ FT	109
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	12635
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	95
44000600	SIDEWALK REMOVAL	SQ FT	1278
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	29
56109210	WATER VALVES TO BE ADJUSTED	EACH	3
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	93
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	473
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	150
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	9897
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	265

\* SPECIALTY ITEM

MODEL: Default  
FILE NAME: 22-00044-01-R5\_Greenville\_Resume\_CAD\_Sheets0325-500.dgn



USER NAME = tkrupe	DESIGNED - TAK/NRS	REVISED - △ 4/1/24
PLOT SCALE = 40,0000' / in.	DRAWN - TAK	REVISED -
PLOT DATE = 4/1/2024	CHECKED - TAK	REVISED -
	DATE - 1/8/24	REVISED -

**BEAUMONT AVENUE RESURFACING  
CITY OF GREENVILLE, ILLINOIS**

**SUMMARY OF QUANTITIES**

SCALE: NTS SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE. 9827	SECTION 22-00044-01-R5	COUNTY	TOTAL SHEETS 35	SHEET NO. 3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 97828	

### SIGN SCHEDULE

STATION	OFFSET	MUTCD TYPE	DESCRIPTION	SIZE (IN X IN)	SIGN PANEL TYPE I (SQ FT)	TELESCOPING SIGN SUPPORT (FOOT)	REMOVE SIGN (SPECIAL) (EACH)
113+67.17	15.89' RT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-9P	AHEAD PLAQUE	24 X 12	2.00		
113+97.89	15.08' RT		STOP FOR PEDESTRIAN				1
114+14.46	14.72' LT		STOP FOR PEDESTRIAN				1
114+62.95	14.56' RT		STOP FOR PEDESTRIAN				1
114+63.39	15.50' RT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
114+71.65	14.93' LT		STOP FOR PEDESTRIAN				1
114+72.14	15.51' LT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
115+69.77	15.07' LT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-9P	AHEAD PLAQUE	24 X 12	2.00		
120+08.51	16.27' RT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-9P	AHEAD PLAQUE	24 X 24	4.00		
121+09.18	15.50' RT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
121+24.34	15.50' RT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
123+40.30	15.50' RT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
123+51.28	15.50' LT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
130+80.67	16.48' RT		STOP FOR PEDESTRIAN				1
130+82.06	15.50' LT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
130+92.02	15.50' LT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-7P	ARROW PLAQUE	24 X 12	2.00		
130+93.21	17.71' LT		STOP FOR PEDESTRIAN				1
132+56.71	16.49' LT	W11-2	PEDESTRIAN	30 X 30	6.25	14.5	
		W16-9P	AHEAD PLAQUE	24 X 12	2.00		
<b>TOTAL</b>					<b>101.0</b>	<b>174.0</b>	<b>6.0</b>

### SIDEWALK SCHEDULE

BEGIN STATION	BEGIN OFFSET	END STATION	END OFFSET	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH (SQ FT)	AGGREGATE BASE COURSE TYPE A 4 INCH (SQ YD)	DETECTABLE WARNINGS (SQ FT)	SIDEWALK REMOVAL (SQ FT)
103+25.74	45.29' RT	103+37.97	35.45' RT	123	14	15	133
103+63.43	28.59' RT	103+83.03	22.96' RT	141	16	10	129
114+08.54	12.34' LT	114+12.89	27.02' LT				60
114+08.90	12.10' RT	114+14.44	18.07' RT				34
114+64.70	26.73' LT	114+69.70	12.00' LT	74	8	10	
114+65.12	13.20' LT	114+69.21	26.72' LT				52
114+66.07	12.01' RT	114+70.70	18.14' RT				26
114+67.39	12.00' RT	114+72.40	18.21' RT	31	4	10	
115+02.02	13.25' LT	115+05.50	26.65' LT				51
120+56.78	13.99' LT	120+71.11	29.62' LT				73
120+89.07	29.80' RT	121+22.09	17.31' RT	242	27	24	196
123+37.10	27.84' LT	123+58.99	24.02' LT	146	16	10	82
123+36.33	20.78' RT	123+53.02	17.55' RT	93	10	10	60
124+10.08	17.21' RT	124+16.29	13.73' RT				17
124+23.97	12.96' RT	124+33.90	25.22' RT				52
130+73.96	28.54' LT	130+99.39	32.23' LT	183	20	10	176
130+74.89	22.94' RT	130+97.64	18.42' RT	143	16	10	137
<b>TOTAL</b>				<b>1,176</b>	<b>131</b>	<b>109</b>	<b>1,278</b>

NOTE: AGGREGATE BASE COURSE TO BE PLACED IN LOCATIONS OF PROPOSED SIDEWALK PRIOR TO PLACING CONCRETE

### FRAME AND VALVE ADJUSTMENTS

STATION	OFFSET	WATER VALVES TO BE ADJUSTED (EACH)	FRAMES AND GRATES TO BE ADJUSTED (EACH)	FRAMES AND LIDS TO BE ADJUSTED (EACH)
101+17.14	RT	1		
101+92.5	RT	1		
103+28.27	RT	1		
103+30.84	LT			1
103+56.91	LT		1	
<b>TOTAL</b>		<b>3</b>	<b>1</b>	<b>1</b>

### PAVEMENT SCHEDULE

STATION	STATION	OFFSET	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-9.5FG, N50 (TON)	HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "C", N50 (TON)	BITUMINOUS MATERIALS (TACK COAT) (POUND)	LONGITUDINAL JOINT SEALANT (FOOT)	HOT-MIX ASPHALT SHOULDERS (SQ YD)	TEMPORARY RAMP (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT (SQ YD)	2 1/2" (SQ YD)
101+00.00	115+00.00	CL	231	277	2,377	1,400		48	59	3,301
115+00.00	134+00.00	CL	355	426	3,648	1,900				5,067
134+00.00	149+07.01	CL	299	359	3,072	1,607		44	53	4,267
147+58.29	147+86.44	LT					29			
<b>TOTAL</b>			<b>885</b>	<b>1,062</b>	<b>9,097</b>	<b>4,907</b>	<b>29</b>	<b>92</b>	<b>112</b>	<b>12,635</b>

MODEL: Default; FILE NAME: P18325\_Greenville\_Beaumont\_ResurfCAD\_Schedule.dgn



USER NAME = tkruop	DESIGNED - TAK/NRS	REVISED - 4/1/24
PLOT SCALE = 40,000' / in.	DRAWN - TAK	REVISED -
PLOT DATE = 4/1/2024	CHECKED - TAK	REVISED -
	DATE - 1/8/24	REVISED -

**BEAUMONT AVENUE RESURFACING  
CITY OF GREENVILLE, ILLINOIS**

<b>QUANTITY SCHEDULES</b>	
SCALE: NTS	SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.U. RTE. 9827	SECTION 22-00044-01-R5	COUNTY BOND	TOTAL SHEETS 35	SHEET NO. 6
CONTRACT NO. 97828				
ILLINOIS FED. AID PROJECT				