

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				*	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				*
CODE NO	ITEM	UNIT		ROADWAY 80% FED 20% STATE MCHENRY 0005	DRAINAGE 80% FED 20% STATE MCHENRY 0005	100% STATE 0005				CODE NO	ITEM		UNIT	ROADWAY 80% FED 20% STATE MCHENRY 0005	DRAINAGE 80% FED 20% STATE MCHENRY 0005	100% STATE 0005	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1				*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	117	117				
	701801																
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10862	10862				*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	76560	76560				
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	10646	10646				*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1200	1200				
70300211	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS - PAINT	SO FT	117	117				*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	975	975				
								*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	186	186				
70300221	TEMPORARY PAVEMENT MARKING - LINE 4"- PAINT	FOOT	76560	76560				*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2105	2105				
70300241	TEMPORARY PAVEMENT MARKING - LINE 6"- PAINT	FOOT	1200	1200					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1270	1270				
									78300202	PAVEMENT MARKER REMOVAL - WATER BLASTING	SQ FT	27584	27584				
									X0326898	CENTER LINE - RUMBLE STRIP - 16"	FOOT	30350	30350				
70300261	TEMPORARY PAVEMENT MARKING - LINE 12"- PAINT	FOOT	975	975					X2010100	TREE LIMB REMOVAL (4 TO 10 INCHES DIAMETER)	EACH	3	3				
									X2020110	GRADING AND SHAPING SHOULDERS	UNIT	766	766				
									X2100002	PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	UNIT	4.96	4.96				
70300281	TEMPORARY PAVEMENT MARKING - LINE 24"- PAINT	FOOT	186	186					X4400503	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT GREATER THAN 10 FEET	FOOT	253	253				
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	36646	36646					X4421817	CLASS D PATCHES, TYPE III, 7 INCH (SPECIAL)	SO YD	40	20	20			
*	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	20	20				X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	116			116		
*	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	4	4				X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	15				
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	341	341				X6700407	ENGINEER'S FIELD OFFICE, TYPE A (D1)	CAL MO	12	12				

\* = SPECIALTY ITEMS

REVISOR: [Signature] REVISION: [Signature] DATE: 4/9/2024