

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FED / 20% STATE	80% FED / 20% STATE	80% FED / 20% STATE	80% FED / 20% STATE
				BRIDGE	BRIDGE	BRIDGE	ROADWAY
				0013	0013	0013	0013
				016-1061	016-0202	016-1053	URBAN
52200020	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	78	78			
58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	82	82			
58700300	CONCRETE SEALER	SQ FT	3828	719	2403	706	
59000200	EPOXY CRACK INJECTION	FOOT	21		21		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	61	61			
59200101	BRIDGE WASHING NO. 1	EACH	1		1		
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1			
66900200	NON -SPECIAL WASTE DISPOSAL	CU YD	85				85
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12				12
66900530	SOIL DISPOSAL ANALYSIS	EACH	1				1
67100100	MOBILIZATION	L SUM	1				1
66901001	REGULATED SUBSTANCES PRE -CONSTRUCTION PLAN	L SUM	1				1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	484				484
66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1				1
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1				1
66901006	REGULATED SUBSTANCES MONITORING	CAL MO	6				6
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	38977				38,977
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	36833				36,833
70307125	TEMPORARY PAVEMENT MARKING - LINE 5" - TYPE IV TAPE	FOOT	2067				2,067

* DENOTES SPECIAL PROVISION **DENOTES SPECIALTY ITEM *** DENOTES SPECIAL PROVISION AND SPECIALTY ITEM

△
△
△
△
△

3/11/2024 11:44:38 AM P:\Projects\202000020204\DISCIPLINE\CH\Working\Sheets\General\20204_SHT_50002.dgn



DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE - 02/28/2023	REVISED -

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE - 02/28/2023	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 2 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
383	D-91-450-20	COOK	201	4
CONTRACT NO. 62L31				
ILLINOIS FED. AID PROJECT				

△ REVISED SHEET 4/9/2024