STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2007-16
Various Counties
Sheet 5 of 51
Contract Number 44949

Schedule of Quantities

PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	DISTRICT 5	DISTRICT 7
MOBILIZATION	L SUM	1.00	0.70	0.30

TRAFFIC CONTROL & PROTECTION	L SUM	1.00	0.70	0.30
SIGN PANEL - TYPE 3	SQ FT	314.25	314.25	0.00
REMOVE SIGN PANEL - TYPE 3	SQ FT	265.00	265.00	0.00
OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A	FOOT	510.00	326.00	184.00
OVERHEAD SIGN STRUCTURE - SPAN, TYPE II- A	FOOT	108.00	0.00	108.00
OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (3'-0" X 7'-0")	FOOT	40.00	40.00	0.00
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	161.70	96.20	65.50
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	8.00	5.00	3.00
REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	20.00	10.00	10.00
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE - SPAN	EACH	14.00	8.00	6.00
GUARDRAIL MARKER, TYPE A	EACH	4.00	4.00	0.00
TERMINAL MARKER - DIRECT APPLIED	EACH	1.00	1.00	0.00
· · · · · · · · · · · · · · · · · · ·				

General Note

All disturbed areas shall receive seeding (Class 2), Mulch, and Fertilizer at the following rates: Ratio 1:1, Rate 270 lb Nutrients/Acre, (90 lb Nitrogen, 90 lb Phosphorus, 90 lb Potassium). Costs for earthwork, seeding, mulch, and fertilizer are included in the cost of IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3.

Revised 2/26/07