

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NUMBER	DESCRIPTION	UNIT	TOTAL URBAN	80% FED. 20% STATE		80% FED. 20% STATE					
				ROADWAY 1000-2A	BRIDGE X080-2A	100% CITY Y030-1E	TRAFFIC SIGNALS Y031-1F	LIGHTING Y030-1E	SFTY-3N		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6							
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2							
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	13	13							
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	7	7							
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4							
60500050	REMOVING CATCH BASINS	EACH	10	10							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1466	1466							
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50	50							
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2							
63200310	GUARDRAIL REMOVAL	FOOT	86	86							
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2							
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	365	365							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10							
*66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1							
67100100	MOBILIZATION	L SUM	1	1							
*66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2							
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1							
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1							
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	244	244							
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1397	1397							
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	608.4	608.4							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,801	17,801							
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,758	1,758							
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,440	1,440							
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	192	192							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1670	1670							
70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	300							
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200	200							
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	202.8	202.8							
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4204	4204							
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	586	586							
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480	480							
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	64	64							
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	80	80							

*SPECIALTY ITEM

PAY CODE NUMBER	DESCRIPTION	UNIT	TOTAL URBAN	80% FED. 20% STATE		80% FED. 20% STATE					
				ROADWAY 1000-2A	BRIDGE X080-2A	100% CITY Y030-1E	TRAFFIC SIGNALS Y031-1F	LIGHTING Y030-1E	SFTY-3N		
78100105	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	EACH	10	10							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1141	1141							
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	60			60					
81200215	CONDUIT EMBEDDED IN STRUCTURE, 1 1/4" DIA., PVC	FOOT	118				118				
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	95			95					
81400100	HANDHOLE	EACH	1						1		
*81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5						5		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1073					730		343	
X0325669	UNIT DUCT, 2*4XLP, 1*4XLP GROUND 1" POLYETHYLENE	FOOT	361							361	
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	3							3	
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8"X8"	EACH	3							3	
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	3							3	
84200700	LIGHTING FOUNDATION REMOVAL	EACH	3							3	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1						1		
X0301828	ENGINEERED BARRIER	SQ YD	138	138							
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	1								
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	342			342					
X0324886	CONDUIT INSTALLED, 1 1/4" DIA., NON-METALLIC	FOOT	730						730		
X0324939	ANCHOR RODS	EACH	16					16			
X0330400	STORM SEWER WATER MAIN 12"	FOOT	456	456							
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1			1					
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1			1					
X8730402	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 19 12 PAIR	FOOT	848						848		
XX004051	LIGHT POLE, ORNAMENTAL	EACH	3							3	
XX004716	LUMINAIRE, METAL HALIDE, SPECIAL, TYPE III, 175 WATT	EACH	6							6	
*Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	16			16					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4							4	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2							2	
Z0041700	PLUG EXISTING STORM SEWERS	EACH	2	2							
X0325670	CONCRETE BRIDGE RAIL, SIDEWALK MOUNTED	FOOT	224			112		112			

*SPECIALTY ITEM

PLOT DATE = 12/15/2006
 FILE NAME = *FILEL*
 PLOT SCALE = *SCALE*
 OPERATOR = *USER*

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06
IDOT REVISIONS	12/13/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

FAP RTE 567 (IL RTE 38)
 SECTION 34X-BR
 DEKALB COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE 10/24/05

DRAWN BY SUTHEARD
 CHECKED BY BOTT

COMPUTER FILE NO. D10800CVR
 PROJECT 05198
 10/25/06-GSJ

GREZZINI & BRADFORD, INC.
 OF SPRINGFIELD
 CIVIL ENGINEERS
 1000 SOUTH MAIN STREET
 SPRINGFIELD, ILLINOIS 62761
 PROFESSIONAL ENGINEERING CORPORATION
 010 100-0000 010 100-0000 010 100-0000 010 100-0000