

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"**

FOOT	LOCATION	DESCRIPTION
220	134+70, 11' LT	- 143+20, 15.5' LT LANE LINE - DASHED WHITE
220	134+70, 21' RT	- 143+20, 16' RT LANE LINE - DASHED WHITE
813	134+70, CL	- 142+83, 5.3' LT EDGELINE - SOLID YELLOW
813	134+70, 10' RT	- 142+83, 5.2' RT EDGELINE - SOLID YELLOW
210	134+70, 1.0' RT	- 142+83, 4.3' LT TURN LANE - DASHED YELLOW
210	134+70, 9.0' RT	- 142+83, 4.2' RT TURN LANE - DASHED YELLOW
74	142+83, 5.2' RT	- 143+20, CL TURN LANE - DOUBLE SOLID YELLOW
74	142+83, 5.4' LT	- 143+20, 5.3' LT CENTERLINE - DOUBLE SOLID YELLOW
218	143+20, 5.3' LT	- 144+29, 5.3' LT CENTERLINE - DOUBLE SOLID YELLOW
120	143+20, CL	- 143+80, 5.3' LT TURN LANE - DOUBLE SOLID YELLOW
25	143+20, 16.5' LT	- 144+27, 16.5' LT LANE LINE - DASHED WHITE
25	143+20, 16.5' RT	- 144+27, 16.5' RT LANE LINE - DASHED WHITE
80	145+25, 16.5' LT	- 148+40, 16.5' LT LANE LINE - DASHED WHITE
80	145+25, 16.5' RT	- 148+40, 16.5' RT LANE LINE - DASHED WHITE
652	145+23, 5.5' RT	- 148+40, 3' LT CENTERLINE - DOUBLE SOLID YELLOW
370	146+52, 5.5' RT	- 148+36, 5.5' LT TURN LANE - DOUBLE SOLID YELLOW
4204		TOTAL

**78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"**

FOOT	LOCATION	DESCRIPTION
47	143+80, 5.5' RT	- 144+27, 5.5' RT TURN LANE - SOLID WHITE
55	144+34, 27' RT	- 144+35, 28' LT CROSSWALK - SOLID WHITE
57	144+40, 27' RT	- 144+41, 30' LT CROSSWALK - SOLID WHITE
69	144+40, 27' RT	- 145+09, 27' RT CROSSWALK - SOLID WHITE
60	144+48, 33' RT	- 145+08, 33' RT CROSSWALK - SOLID WHITE
33	144+53, 41' LT	- 144+86, 45' LT CROSSWALK - SOLID WHITE
29	144+56, 48' LT	- 144+84, 51' LT CROSSWALK - SOLID WHITE
54	145+09, 27' RT	- 145+13, 27' LT CROSSWALK - SOLID WHITE
55	145+15, 28' RT	- 145+19, 27' LT CROSSWALK - SOLID WHITE
127	145+25, 5.5' LT	- 146+52, 5.5' LT TURN LANE - SOLID WHITE
586		TOTAL

**78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"**

FOOT	LOCATION	DESCRIPTION
108	144+34, 27' RT	- 144+35, 28' LT CROSSWALK BARS - WHITE
120	144+48, 33' RT	- 145+08, 33' RT CROSSWALK BARS - WHITE
60	144+56, 48' LT	- 144+84, 51' LT CROSSWALK BARS - WHITE
108	145+09, 27' RT	- 145+13, 27' LT CROSSWALK BARS - WHITE
84	146+93	- 148+33 TURN LANE DIAGONALS - YELLOW
480		TOTAL

**78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"**

FOOT	LOCATION	DESCRIPTION
32	144+29, 5' LT	- 144+29, 27' RT STOP BAR - WHITE
32	145+23, 5' RT	- 145+23, 27' LT STOP BAR - WHITE
64		TOTAL

**78100105 RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)**

EACH	LOCATION	DESCRIPTION
2	140+55, 6.5' LT & RT	- BI-DIRECTIONAL AMBER
2	140+55, 16.5' LT & RT	- MONO-DIRECTIONAL WHITE
2	140+95, 6.5' LT & RT	- BI-DIRECTIONAL AMBER
2	141+35, 6.5' LT & RT	- BI-DIRECTIONAL AMBER
2	141+35, 16.5' LT & RT	- MONO-DIRECTIONAL WHITE
10		TOTAL

**78300100 PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION	DESCRIPTION
518	135+87.5, CL	- 143+65, LT - DOUBLE YELLOW
66	135+87.5, RT	- 143+80, RT - WHITE SKIP DASH
74	138+75, LT	- 147+65, LT - WHITE SKIP DASH
153	141+50, CL	- 143+80, LT - DOUBLE YELLOW

**PRIOR TO STAGE II**

FOOT	LOCATION	DESCRIPTION
78	134+70, CL	- 135+87.5, CL - DOUBLE YELLOW
20	134+70, RT	- 137+10, RT - WHITE SKIP DASH
11	137+50, LT	- 138+75, LT - WHITE SKIP DASH
64	145+24, LT	- 146+52, LT - WHITE SOLID
29	145+24, RT	- 145+67, RT - DOUBLE YELLOW
122	146+52, RT	- 148+35, LT - DOUBLE YELLOW
6	147+65, LT	- 148+35, LT - WHITE SKIP DASH
1141		TOTAL

**81012600 CONDUIT IN TRENCH, 2" DIA., PVC**

FOOT	LOCATION	DESCRIPTION
18	STA. 140+35, 45' RT.	- STA. 140+38, 40' RT. (SN 019-0044)
42	STA. 141+55, 40' LT.	(SN 019+0044) - STA. 141+82, 45' LT.
60		TOTAL

**81200215 CONDUIT EMBEDDED IN STRUCTURE, 1 1/4" DIA., PVC**

FOOT	LOCATION	DESCRIPTION
118	SN 019-0044	
118		TOTAL

**81200230 CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC**

FOOT	LOCATION	DESCRIPTION
95	SN 019-0044	
95		TOTAL

**81400100 HANDHOLE**

EACH	LOCATION	DESCRIPTION
1	134+90, 38' LT	
1		TOTAL

**CONCRETE HANDHOLE**

EACH	LOCATION	DESCRIPTION
1	134+70, 27' LT	
1	137+40, 30' LT	
1	140+10, 32' LT	
1	141+65, 32' LT	
1	143+15, 32' LT	
5		TOTAL

**81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK**

FOOT	LOCATION	DESCRIPTION
90	134+70	- 143+20, LT & RT
122	134+70	- 143+20, LT & RT
270	134+70, 27' LT	- 137+40, 30' LT
270	137+40, 30' LT	- 140+10, 32' LT.
28	140+10, 32' LT	- SN 019-0044
12	SN 019-0044	- 141+65 - 32' LT
150	141+65, 32' LT	- 143+15 - 32' LT
131	142+83	- 143+20, RT
1073		TOTAL

**UNIT DUCT, 2#4XLP, 1#4XLP GROUND 1" POLYETHYLENE**

FOOT	LOCATION	DESCRIPTION
99	134+90, 38' LT	- 135+78.72, 42' LT
126	135+78.72, 42' LT	- 136+99.67, 42' LT
136	136+99.67, 42' LT	- 138+30.12, 42' LT
361		TOTAL

**82102250 LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT**

EACH	LOCATION	DESCRIPTION
1	135+78.72, 42' LT	
1	136+99.67, 42' LT	
1	138+30.12, 42' LT	
3		TOTAL

**83600357 LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8"**

EACH	LOCATION	DESCRIPTION
1	135+78.72, 42' LT	
1	136+99.67, 42' LT	
1	138+30.12, 42' LT	
3		TOTAL

**84200600 REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE**

EACH	LOCATION	DESCRIPTION
1	135+78.72, 42' LT	
1	136+99.67, 42' LT	
1	138+30.12, 42' LT	
3		TOTAL

**84200700 LIGHTING FOUNDATION REMOVAL**

EACH	LOCATION	DESCRIPTION
1	135+78.72, 42' LT	
1	136+99.67, 42' LT	
1	138+30.12, 42' LT	
3		TOTAL

**89502375 REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT**

EACH	LOCATION	DESCRIPTION
1	134+70	- 143+15, LT
1		TOTAL

**X0321556 SANITARY MANHOLES TO BE ADJUSTED**

EACH	LOCATION	DESCRIPTION
1	142+68.91, 17.42' RT	
1		TOTAL

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06
IDOT REVISIONS	12/13/06
IDOT REVISIONS	2/01/07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP RTE 567 (IL RTE 38)  
 SECTION 34X-BR  
 DEKALB COUNTY

VERT. SCALE: 1" = 20'  
 HORIZ. SCALE: 1" = 40'  
 DATE: 10/24/05

DRAWN BY: SUTHEARD  
 CHECKED BY: BOTT

COMPUTER FILE NO. D10800CVR  
 PROJECT 05198  
 10/25/06-GSJ

GREENE & BRADFORD, INC.  
 OF SPRINGFIELD  
 CONSULTING ENGINEERS  
 300 SOUTH MAIN STREET  
 SPRINGFIELD, ILLINOIS 62761  
 PROFESSIONAL ENGINEERS IN ILLINOIS  
 PROFESSIONAL ENGINEERS IN MISSOURI  
 PROFESSIONAL ENGINEERS IN INDIANA  
 (312) 424-4400 FAX (312) 424-4401 www.greenengr.com

PLOT DATE = 2/2/2007  
 FILE NAME = #FILEL#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#  
 OPERATOR = #USERS#