GENERAL NOTES

CONTRACT NO. 64800

| ROUTE NO. | SEC. | COUNTY | TOTAL | SHEET NO. |
|---------------------|----------|---------|-------|--------------|
| FAP 303 (IL 173) | 130BR-4 | Boone | 147 | 5 |
| FED ROAD DIST. NO. | ILLINOIS | PROJECT | | |
| Contract #64900 | | | | |

Commitments (Con't)

- 4. The proposed right of way, easements, and construction limits shall remain as shown in the project plans of the Design Report to avoid further wetland impacts and to avoid impacts to the bike path.
- 5. No fill will be placed in or along the stream between the IL 173 roadway and the bike path (old railroad bed) to avoid additional wetland impacts.
- 6. The Phase II Special Provisions shall specify the following for the temporary runaround area.
 - a) Before the temporary runaround is installed, the top 12 inches of top soil shall be removed and stockpiled.
 - b) After completion of the roadway project, the entire temporary runaround and supporting fill shall be removed.
 - c) The area shall be deep-plowed with a single bottom plow.
 - d) The area shall be filled back with the original topsoil.
 - e) The area shall be reconstructed to match the existing field contours.
- 7. The realigned stream bank will be protected with Turf Reinforcement Mat (TRM). It will be seeded with Seeding Class 2 (Modified). Seeding Class 2 (Modified) will include the grass species listed in the Standard Specifications for Road and Bridge Construction (Jan. 1, 2007) and add 1.0 lb./acre of Rice Cut Grass (Leersia Oryzoides).
- 8. Prior to the beginning of construction, the IDOT Resident Engineer shall coordinate with the Bureau of Program Development, Land Acquisition Unit to ensure that a Temporary Use Permit has been obtained from the Boone County Conservation District (BCCD) for any necessary earthwork conducted on Conservation District property located on the south side of IL 173.
- 9. Prior to the beginning of construction, the IDOT Resident Engineer shall contact the Boone County Conservation District at 815/547-7935 to arrange a coordination meeting to discuss the project and to photo document the preconstruction conditions on the Conservation District.
- 10. At the request of the Boone County Conservation District, special signage shall be provided on the Long Prairie Recreational Trail located south of and parallel to IL 173. Two signs, viewable from both travel directions on the Long Prairie Trail, shall be provided in advance of the Temporary Use Permit area. The signs shall indicate "Caution! Construction adjacent to trail in progress" or similar wording as approved by the Conservation District.
- 11. The Boone County Conservation District has specified Burr Oak, White Oak or Hickory for preferred replacement trees on their property. The IDOT Resident Engineer and/or the District 2 Landscape Architect should complete any necessary coordination with the Boone County Conservation District prior to tree replacement, especially if there are availability problems or size limitations with the preferred species listed above.
- 12. All areas specified for Class 4 seed mix shall have Class 5 seed mix applied in addition to the Class 4 mix.
- 13. The contractor shall notify property owner, Donald J Meier, at 815-999-2597 to discuss the possibility of disposing of any clean fill generated by the project on Mr. Meier's property. Mr. Meier has expressed an interest in obtaining clean fill if it is available.

Program #5 (Arch. Size) Enlarge 200% Enlarge 107%