

# SUMMARY OF QUANTITIES

CONTRACT NO. 64800

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	130BR-4	BOONE	147	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	TOTAL	80%-FED 20%-STATE NHS  1000 ROADWAY	80%-FED 20%-STATE BR  X081-2A BRIDGE
42001300	PROTECTIVE COAT	SO YD	687		687
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	55.3		55.3
44000100	PAVEMENT REMOVAL	SO YD	8110	8110	
44002400	CURB REMOVAL (SPECIAL)	FOOT	858	858	
44004300	PAVEMENT BREAKING	SO YD	626	626	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	671	671	
48101300	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	TON	253	253	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	2256	2256	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	417.2		417.2
50300225	CONCRETE STRUCTURES	CU YD	73.7		73.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	203		203
50300260	BRIDGE DECK GROOVING	SO YD	549		549
50300280	CONCRETE ENCASEMENT	CU YD	10		10
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	771.5		771.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	54870		54870
51201105	FURNISH METAL SHELL PILES 14"	FOOT	992		992
51203200	TEST PILE METAL SHELLS	EACH	3		3
51500100	NAME PLATES	EACH	1		1
54210513	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 18"	FOOT	40	40	
54213447	END SECTIONS 12"	EACH	4	4	
54213453	END SECTIONS 18"	EACH	2	2	
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	1	1	
5422D018	PIPE CULVERTS, CLASS D, TYPE 2 18" (TEMPORARY)	FOOT	43	43	
5423D060	PIPE CULVERTS, CLASS D, TYPE 3 60" (TEMPORARY)	FOOT	336	336	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	82		82
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4		4
60100945	PIPE DRAINS 12"	FOOT	122	122	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	206	53	153
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	4	4	
60900515	CONCRETE THRUST BLOCKS	EACH	4	4	
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	100	100	
61101011	STORM SEWERS PROTECTED, CLASS A, 10"	FOOT	100	100	
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	100	100	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY
DATE		

## SUMMARY OF QUANTITIES

PLOT DATE: Fri Dec 15 08:46:22 2006  
 FILE NAME: c:\p\proj\15\203022\ab3022-cr.dgn  
 USER: g1111111