CONTRACT NO. 64800

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 303 | 13088-4 | BOONE | 147 | 15 |
| STA. _____ | | TO STA. _____ | | |
| FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT | | |

# SCHEDULE OF QUANTITIES

44002400 CURB REMOVAL (SPECIAL)

| FOOT | LOCATION | | | |
|---|---|---|---|---|
| 503 | STA. 437+35 | TO | 442+38 | LT |
| 355 | STA. 437+88 | TO | 441+43 | RT |
| 858 TOTAL | | | | |

44004300 PAVEMENT BREAKING

| SQ. YD. | LOCATION | | |
|---|---|---|---|
| 390 | STA. 437+50 | TO | 438+85 |
| 236 | STA. 441+18.5 | TO | 442+00 |
| 626 TOTAL | | | |

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 440+34.95 | IL 173 BRIDGE |
| 1 TOTAL | | |

54210513 PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM EQUIVALENT ROUND - SIZE 18"

| FOOT | LOCATION | |
|---|---|---|
| 40 | STA. 114+50 | AR CULVERT |
| 40 TOTAL | | |

54213447 END SECTIONS 12"

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 439+12.27 | BRIDGE DRAIN LT |
| 1 | STA. 439+05.22 | BRIDGE DRAIN RT |
| 1 | STA. 440+70.78 | BRIDGE DRAIN LT |
| 1 | STA. 440+63.73 | BRIDGE DRAIN RT |
| 4 TOTAL | | |

54213453 END SECTIONS 18"

| EACH | LOCATION | |
|---|---|---|
| 2 | STA. 107+50 | AR CULVERT |
| 2 TOTAL | | |

54214293 END SECTIONS, EQUIVALENT ROUND - SIZE 18"

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 114+50 | AR CULVERT |
| 1 TOTAL | | |

5422D018 PIPE CULVERTS, CLASS D, TYPE 2 18" (TEMPORARY)

| FOOT | LOCATION | |
|---|---|---|
| 43 | STA. 107+50 | AR CULVERT |
| 43 TOTAL | | |

5423D060 PIPE CULVERTS, CLASS D, TYPE 3 60" (TEMPORARY)

| FOOT | LOCATION | |
|---|---|---|
| 336 | STA. 111+80 | AR CULVERT (6 EA. @ 56') |
| 336 TOTAL | | |

60100060 CONCRETE HEADWALL FOR PIPE DRAIN

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 439+24.77 | WEST ABUTMENT LT |
| 1 | STA. 439+19.15 | WEST ABUTMENT RT |
| 1 | STA. 440+56.85 | EAST ABUTMENT LT |
| 1 | STA. 440+49.23 | EAST ABUTMENT RT |
| 4 TOTAL | | |

60100945 PIPE DRAINS 12"

| FOOT | LOCATION | |
|---|---|---|
| 32 | STA. 439+12.27 | BRIDGE DRAIN LT |
| 25.5 | STA. 439+05.22 | BRIDGE DRAIN RT |
| 33.5 | STA. 440+70.78 | BRIDGE DRAIN LT |
| 31 | STA. 440+63.73 | BRIDGE DRAIN RT |
| 122 TOTAL | | |

60109580 PIPE UNDERDRAINS FOR STRUCTURES 4"

| FOOT | LOCATION | |
|---|---|---|
| 13.25 | STA. 439+24.77 | WEST ABUTMENT LT |
| 13.25 | STA. 439+19.15 | WEST ABUTMENT RT |
| 13.25 | STA. 440+56.85 | EAST ABUTMENT LT |
| 13.25 | STA. 440+49.23 | EAST ABUTMENT RT |
| 53 TOTAL | | |

60236200 INLETS, TYPE A, TYPE 8 GRATE

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 114+50 | STAGE I |
| 1 TOTAL | | |

60500060 REMOVING INLETS

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 114+50 | STAGE III |
| 1 TOTAL | | |

60900315 TYPE D INLET BOX, STANDARD 609006

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 439+12.27 | BRIDGE DRAIN LT |
| 1 | STA. 439+05.22 | BRIDGE DRAIN RT |
| 1 | STA. 440+70.78 | BRIDGE DRAIN LT |
| 1 | STA. 440+63.73 | BRIDGE DRAIN RT |
| 4 TOTAL | | |

60900515 CONCRETE THRUST BLOCKS

| EACH | LOCATION | |
|---|---|---|
| 1 | STA. 439+12.27 | BRIDGE LT |
| 1 | STA. 439+05.22 | BRIDGE RT |
| 1 | STA. 440+70.78 | BRIDGE LT |
| 1 | STA. 440+63.73 | BRIDGE RT |
| 4 TOTAL | | |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Fri Feb 23 09:46:25 2007
FILE NAME = c:\projects\vse\p203082\d203082cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = chrisfrse