CONTRACT NO. 64C30

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(81-1) M-4	ROCK ISLAND	33	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200100 EARTH EXCAVATION

CU. YD.	LOCATION				REMARKS
26.4		1034+25	TO	1048+35	RAMP AND SHOULDER
80.0		827+50	TO	831+50	SHOULDER BEHIND GUARDRAIL
TOTAL 106.4					

20400800 FURNISHED EXCAVATION

CU. YD.	LOCATION				REMARKS
157.0		1034+25	TO	1048+35	RAMP AND SHOULDER
7.0		827+50	TO	831+50	SHOULDER BEHIND GUARDRAIL
TOTAL 164.0					

25000210 SEEDING, CLASS 2A

ACRE	LOCATION				REMARKS
0.5		1034+25	TO	1048+35	RAMP AND SHOULDER
0.2		827+50	TO	831+50	EARTH BEHIND GUARDRAIL
TOTAL 0.7					

25000750 MOWING

ACRE	LOCATION				REMARKS
0.5		1034+25	TO	1048+35	RAMP AND SHOULDER
0.2		827+50	TO	831+25	EARTH BEHIND GUARDRAIL
TOTAL 0.7					

25100115 MULCH, METHOD 2

ACRE	LOCATION				REMARKS
0.5		1034+25	TO	1048+35	RAMP AND SHOULDER
0.2		827+50	TO	831+25	EARTH BEHIND GUARDRAIL
TOTAL 0.7					

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION				REMARKS
108.5		1034+25	TO	1048+35	RAMP AND SHOULDER
41.2		827+50	TO	831+25	EARTH BEHIND GUARDRAIL
TOTAL 149.7					

28100105 STONE RIPRAP CLASS A3

SQ YD	LOCATION		REMARKS
	SW RAMP		
1.0	RT	1050+60	END OF PIPE UNDERDRAIN, 3' X 3'
TOTAL 1.0			

28100107 STONE RIPRAP CLASS A4

SQ YD	LOCATION		REMARKS
	SW RAMP		
7.1	RT	1048+05	DOWNSTREAM END OF CULVERT, 8' X 8'
TOTAL 7.1			

28200200 FILTER FABRIC

SQ YD	LOCATION		REMARKS
	IL 2		
7.1	RT	1048+05	DOWNSTREAM END OF CULVERT
1.0	RT	1050+60	END OF PIPE UNDERDRAIN
TOTAL 8.1			

40600845 POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90

TON	LOCATION				REMARKS
	RAMP				
376.5		1034+25	TO	1048+15	RAMP MAINLINE WITH GRADE CORRECTION
TOTAL 376.5					

40600990 TEMPORARY RAMP

SQ YD	LOCATION				REMARKS
	RAMP				
33.7		1034+25	TO	1034+35	TOP OF RAMP STAGE I AND STAGE II
33.7		1048+00	TO	1048+10	BOTTOM OF RAMP STAGE I AND STAGE II
TOTAL 67.4					

PLOT DATE = Thu Jan 25 15:44:22 2007
FILE NAME = C:\pwworking\USR\2265\d0172265cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = grantpm