

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(81-1) M-4	ROCK ISLAND	33	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

ION	LOCATION	REMARKS
HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50		
RAMP		
140.4	1034+25 TO 1048+35	RAMP SHOULDERS ADJACENT TO MAINLINE LT
183.2	1034+25 TO 1048+35	RAMP SHOULDERS ADJACENT TO MAINLINE RT
48.3	827+50 TO 831+25	SHOULDER ADJACENT TO GUARDRAIL
TOTAL		
372.0		

ION	LOCATION	REMARKS
HOT-MIX ASPHALT SHOULDERS, 6 1/2"		
RAMP		
575.6	827+50 TO 832+15	SHOULDER ADJACENT TO GUARDRAIL
TOTAL		
575.6		

ION	LOCATION	REMARKS
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90		
RAMP		
243.2	1034+25 TO 1048+35	RAMP MAINLINE
TOTAL		
243.2		

ION	LOCATION	REMARKS
STEEL PLATE BEAM GUARD RAIL, TYPE A		
EQUI		
150.0	829+38 TO 830+86	
TOTAL		
150.0		

ION	LOCATION	REMARKS
HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"		
RAMP		
548.5	1034+25 TO 1035+60	RAMP MAINLINE WITH GORE AREA
353.5	1047+00 TO 1048+35	RAMP MAINLINE WITH GORE AREA
TOTAL		
902.1		

ION	LOCATION	REMARKS
TRAFFIC BARRIER TERMINAL, TYPE 6B		
EACH		
1.0	830+85 TO 831+43	
TOTAL		
1.0		

ION	LOCATION	REMARKS
PAVED SHOULDER REMOVAL		
RAMP		
298.00	827+50 TO 832+15	SHOULDER ADJACENT TO GUARDRAIL
TOTAL		
298.0		

ION	LOCATION	REMARKS
TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)		
EACH		
1.0	828+86 TO 829+38	
TOTAL		
1.0		

ION	LOCATION	REMARKS
AGGREGATE SHOULDERS, TYPE A		
RAMP		
159.0	RT 1034+25 TO 1048+35	RAMP MAINLINE
150.75	LT 1036+00 TO 1047+50	RAMP MAINLINE
TOTAL		
309.8		

ION	LOCATION	REMARKS
TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)		
EACH		
2.0	831+28 TO 833+00	
TOTAL		
2.0		

ION	LOCATION	REMARKS
GUARDRAIL REMOVAL		
EQUI		
580.0	827+83 TO 833+53	
TOTAL		
580.0		

PLOT DATE : Thu Jan 25 15:44:22 2007
 FILE NAME : C:\projects\207286\207286.dgn
 PLOT SCALE : 50.0000 / IN
 USER NAME : gantep