

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(46-2HB)I	KANKAKEE	10	3
FED. ROAD DIST. NO. ILLINOIS			NON-FED. AID PROJECT	

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	100% STATE MCHD CLAIM #723628	100% CONT MAINT 0-00857-3017
50102400	CONCRETE REMOVAL	CU YD	1.4	1.3	0.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.4	1.3	0.1
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5990	5391	599
50501110	STRUCTURAL STEEL REMOVAL	POUND	6350	5715	635
67100100	MOBILIZATION	L SUM	1	0.9	0.1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1	0.9	0.1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	0.9	0.1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.9	0.1
70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	810	729	81
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	267	240	27
70400100	TEMPORARY CONCRETE BARRIER	FOOT	630	567	63
X7011008	TRAFFIC CONTROL AND PROTECTION, FOR ALTERNATE ROUTE SIGNING	CAL MO	0.5	0.5	0.0
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	0.9	0.1
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	0.9	0.1

DATE: 12/20/2006
c:\projects\cm01n07\cm317\det01s.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAI ROUTE 57 (I-57) SECTION: (46-2HB)I
KANKAKEE COUNTY
S.N. 046-0014 (SB)
STA. 311+37.70