

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	47R5-12	VERMILION	24	10

SCHEDULES OF QUANTITIES

SHEET 3 OF 5

HOT MIX ASPHALT CALCULATIONS

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	HMASC THICKNESS (INCHES)	LEV BIND THICKNESS (INCHES)	40603340 P HMA SC MIX "D" N70 (TONS)	40600635 LEV BIND MM N70 (TON)	40600100 BIT MATLS PR CT (GAL)	40600300 AGG PR CT (TONS)	
2627+89.00		2743+00.00	11511.0	48	61392.0	1.5	0.75	5156.9	2578.5	6139.2	122.8	
								SUB-TOTAL =	5156.9	2578.5	6139.2	122.8
 <u>SHOULDERS (A1 SEAL COAT)</u>												
NB 2627+89.00		NB 2743+00.00	11511.0	8	10232.0	N/A	N/A	N/A	N/A	1023.2	N/A	
SB 2627+89.00		SB 2743+00.00	11511.0	8	10232.0	N/A	N/A	N/A	N/A	1023.2	N/A	
								SUB-TOTAL =	N/A	N/A	2046.4	N/A
 <u>SIDE ROADS (A1 SEAL COAT)</u>												
16 TH STREET			30.0	VAR.	928.0	N/A	N/A	N/A	N/A	92.8	N/A	
TR 900 N (RT 2662+63)			36.0	VAR.	796.0	N/A	N/A	N/A	N/A	79.6	N/A	
TOWNSHIP ROAD (LT 2665+51.7)			35.0	VAR.	781.0	N/A	N/A	N/A	N/A	78.1	N/A	
MAPLE GROVE ROAD (LT 2705+41.8)			29.0	VAR.	613.0	N/A	N/A	N/A	N/A	61.3	N/A	
								SUB-TOTAL =	N/A	N/A	311.8	N/A
								TOTAL =	5156.9	2578.5	8497.4	122.8
								USE =	5157.0	2579.0	8497.0	123.0