

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57&74	*	**	151	16

* D5 CABLE GUARD 2007-2
 ** CHAMPAIGN, DEWITT & DOUGLAS

SCHEDULES OF QUANTITIES

EARTHWORK ANALYSIS

<u>LOCATION</u>	20200100 EARTH EXCAVATION (CU. YD.)	EARTH EX. SHRINK(25%) (CU. YD.)	EMBANKMENT (CU. YD.)	20400800 FURNISHED EXCAVATION (CU. YD.)
<u>DOUGLAS COUNTY</u>				
LOC #1 TUSCOLA (I-57 SBDL SHOULDER) LT. STA. 466+50 - 504+00	442.0	331.5	678.7	348.0
<u>CHAMPAIGN COUNTY</u>				
LOC #2 PESOTUM (I-57 SBPL MEDIAN) LT. STA. 173+50 - 251+00	2245.0	1684.0	4055.0	2371.0
<u>DEWITT COUNTY</u>				
LOC #3 FARMER CITY (I-74 EBPL MEDIAN) RT. STA. 711+50 - 744+50	172.0	129.0	1451.7	1323.0
<u>TOTALS =</u>	<u>2859.0</u>			<u>4042.0</u>

SEEDING SUMMARY

<u>LOCATION</u>	25000200 SEEDING CLASS 2 (ACRE)	25000400 NITROGEN (POUND)	25000500 PHOSPHORUS (POUND)	25000600 POTASSIUM (POUND)	25100115 MULCH METHOD 2 (ACRE)	28000250 TEMP. EROS. CTL SEEDING (POUND)
<u>DOUGLAS COUNTY</u>						
LOC #1 TUSCOLA (I-57 SBDL SHOULDER) LT. STA. 466+50 - 504+00	2.1	189.0	189.0	189.0	2.1	210.0
<u>CHAMPAIGN COUNTY</u>						
LOC #2 PESOTUM (I-57 SBPL MEDIAN) LT. STA. 173+50 - 251+00	7.0	630.0	630.0	630.0	7.0	700.0
<u>DEWITT COUNTY</u>						
LOC #3 FARMER CITY (I-74 EBPL MEDIAN) RT. STA. 711+50 - 744+50	2.4	216.0	216.0	216.0	2.4	240.0
<u>TOTALS =</u>	<u>11.5</u>	<u>1035.0</u>	<u>1035.0</u>	<u>1035.0</u>	<u>11.5</u>	<u>1150.0</u>