

66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

| LOCATION | | QUANTITY (EACH) |
|------------|----------|-----------------|
| STATION | OFFSET | |
| 2124+00.00 | 30.00 RT | 1 |
| 2124+00.00 | 25.00 LT | 1 |
| 2125+50.00 | 70.00 LT | 1 |
| 2126+50.00 | 70.00 RT | 1 |
| 2126+50.00 | 70.00 LT | 1 |
| 2127+50.00 | 70.00 RT | 1 |
| 2128+50.00 | 30.00 RT | 1 |
| 2128+50.00 | 25.00 LT | 1 |
| TOTAL = | | 8 |

67000400 ENGINEER'S FIELD OFFICE, TYPE A

| LOCATION | QUANTITY (CAL. MONTH) |
|----------|-----------------------|
| JOB SITE | 6 |
| TOTAL = | 6 |

67100100 MOBILIZATION

| LOCATION | QUANTITY (L SUM) |
|----------|------------------|
| JOB SITE | 1 |
| TOTAL = | 1 |

70101830 TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21

| LOCATION | QUANTITY (L SUM) |
|----------|------------------|
| JOB SITE | 1 |
| TOTAL = | 1 |

78001120 PAINT PAVEMENT MARKING - LINE 5'

| LOCATION | QUANTITY (FOOT) |
|---------------------------------|-----------------|
| STATION | |
| 2123+95.00 TO 2128+40.00 CENTER | 112.0 |
| 2123+95.00 TO 2128+40.00 LEFT | 445.0 |
| 2123+95.00 TO 2128+40.00 RIGHT | 445.0 |
| TOTAL = | 1002.0 |

78200410 GUARDRAIL MARKERS, TYPE A

| LOCATION | | QUANTITY (EACH) |
|------------|--------|-----------------|
| STATION | OFFSET | |
| 2124+85.00 | RT | 1 |
| 2125+40.00 | | 1 |
| 2125+95.00 | | 1 |
| 2126+50.00 | | 1 |
| 2127+05.00 | | 1 |
| 2127+60.00 | LT | 1 |
| 2124+90.00 | | 1 |
| 2125+45.00 | | 1 |
| 2126+00.00 | | 1 |
| 2126+55.00 | | 1 |
| 2127+10.00 | 1 | |
| 2127+65.00 | 1 | |
| TOTAL = | | 12 |

78201000 TERMINAL MARKER - DIRECT APPLIED

| LOCATION | | QUANTITY (EACH) |
|------------|----------|-----------------|
| STATION | OFFSET | |
| 2124+85.00 | 16.00 RT | 1 |
| 2124+90.00 | 16.00 LT | 1 |
| 2127+60.00 | 16.00 RT | 1 |
| 2127+65.00 | 16.00 LT | 1 |
| TOTAL = | | 4 |

35501316 HOT-MIX ASPHALT BASE COURSE, 8"

| LOCATION | QUANTITY (SQ. YD.) |
|--------------------------|--------------------|
| STATION | |
| 2125+75.00 TO 2126+75.00 | 223.0 |
| TOTAL = | 223.0 |

35600708 HOT-MIX ASPHALT BASE COURSE WIDENING, 8"

| LOCATION | QUANTITY (SQ. YD.) |
|--------------------------|--------------------|
| STATION | |
| 2124+45.00 TO 2125+75.00 | 58.0 |
| 2126+75.00 TO 2127+90.00 | 52.0 |
| TOTAL = | 110.0 |

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

| LOCATION | QUANTITY (TON) |
|--------------------------|----------------|
| STATION | |
| 2124+45.00 TO 2124+90.00 | 8.7 |
| 2124+90.00 TO 2127+45.00 | 48.6 |
| 2127+45.00 TO 2127+90.00 | 8.7 |
| TOTAL = | 66.0 |

40600625 LEVELING BINDER (MACHINE METHOD), N50

| LOCATION | QUANTITY (TON) |
|--------------------------|----------------|
| STATION | |
| 2124+45.00 TO 2124+90.00 | 5.8 |
| 2124+90.00 TO 2127+45.00 | 32.4 |
| 2127+45.00 TO 2127+90.00 | 5.8 |
| TOTAL = | 44.0 |

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: NONE
DATE: 08/2004

DRAWN BY: FML
CHECKED BY: JH