

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	SIRS-5,TS-7),L	SANGAMON	78	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

	F	HSIP		
ROADWAY	INTERSECTION OF JEFFERSON ST. AND VETERANS PKWY	INTERSECTION OF JEFFERSON ST. AND CHURCHILL DR.	STREET LIGHTING TO STA. 143+00	SIDEWALK
80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY	90% FEDERAL 10% STATE	50% STATE 50% CITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				1000	Y031-1F	Y031-1F	Y030-1E	SFTY-1B
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SO YD	15	15				
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SO YD	25	25				
44201294	CLASS B PATCH EXPANSION JOINT	FOOT	572	572				
44213000	PATCHING REINFORCEMENT	SO YD	1255	1255				
44213100	PAVEMENT FABRIC	SO YD	400	400				
44213200	SAW CUTS	FOOT	11,608	11,608				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	74	74				
48203100	HOT-MIX ASPHALT SHOULDERS	TON	142	142				
60624600	CORRUGATED MEDIAN	SO FT	1057	1057				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	200	200				
* 63100089	TRAFFIC BARRIER TERMINAL TYPE 6B	EACH	2	2				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2				
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	184	184				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2.25	0.5	0.5	0.5	0.25
67100100	MOBILIZATION	L SUM	1	0.3	0.2	0.2	0.2	0.1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.3	0.2	0.2	0.2	0.1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.3	0.2	0.2	0.2	0.1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.3	0.2	0.2	0.2	0.1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.3	0.2	0.2	0.2	0.1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.3	0.2	0.2	0.2	0.1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1888	1888				
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SO FT	156	156				
70300230	TEMPORARY PAVEMENT MARKING LINE 5"	FOOT	6132	6132				
70300240	TEMPORARY PAVEMENT MARKING LINE 6"	FOOT	728	728				
70300260	TEMPORARY PAVEMENT MARKING LINE 12"	FOOT	201	201				
70300280	TEMPORARY PAVEMENT MARKING LINE 24"	FOOT	114	114				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	208	208				

* SPECIALTY ITEMS

Rev. 4-5-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION (SIRS-5, TS-7), L
SANGAMON COUNTY

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
DATE

PLOT DATE : *DATE*
FILE NAME : *FILE#*
PLOT SCALE : *SCALE*
REFERENCE : *REF#*