

F.A.P. SECTION		COUNTY		TOTAL SHEETS		SHEET NO.	
67	SIRS-5, TS-7), L	SANGAMON		78	18C		
STA.				TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT				

PAVEMENT PATCHING SCHEDULE FOR JEFFERSON ST.

LOCATION	EB/WB	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	CLASS A			CLASS B			TIE BARS (EACH)	DOWL BARS (EACH)	PAVEMENT FABRIC (SQ YD)	PATCHING REINFORCEMENT (SQ YD)	SAW CUT (FOOT)
					TYPE 2 (SQ YD)	TYPE 3 (SQ YD)	TYPE 4 (SQ YD)	TYPE 2 (SQ YD)	TYPE 3 (SQ YD)	TYPE 4 (SQ YD)					
147+50 TO 150+00	WB														
PL		6	12	8	8								8	60	
TL		6	12	8	8								8	60	
TL		6	12	8	8								8	60	
DL		6	12	8	8								8	60	
PL		6	12	8	8								8	60	
TL		6	12	8	8								8	60	
PL		6	12	8	8								8	60	
DL		6	12	8	8								8	60	
PL		6	12	8	8								8	60	
DL		6	12	8	8								8	60	
WEST BOUND TOTAL					599	32	0	168	0	0	0	378	168	631	5632
TOTAL					1191	64	*	400	*	*	0	900	400	1255	11608

SCHEDULE IS ONLY A GUIDE AND SHOULD BE VERIFIED BY THE ENGINEER IN THE FIELD  
 \* MINIMUM QUANTITIES ARE INCLUDED IN THE SUMMARY OF QUANTITIES TO ESTABLISH A UNIT BID PRICE SHOULD PATCHING QUANTITIES VARY FROM THOSE SHOWN IN THIS TABLE.

LEGEND
TL = TURN LANE
DL = DRIVING LANE
PL = PASSING LANE
EB = EAST BOUND
WB = WEST BOUND

PLOT DATE = 3/27/2007  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = jhugh1/rp1

▲ ADDED SHEET 4-5-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAP 67 (IL 97/ JEFFERSON ST)  
 SECTION S( RS-5, TS-7), L  
 SANGAMON COUNTY  
 SCALE: VERT. \_\_\_\_\_  
 DATE \_\_\_\_\_ HORIZ. \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_