

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	S(RS-5, TS-7)L	SANGAMON	78	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F	HSIP			
ROADWAY	INTERSECTION OF JEFFERSON ST. AND VETERANS PKWY	INTERSECTION OF JEFFERSON ST. AND CHURCHILL DR.	STREET LIGHTING STA. 126+50 TO STA. 143+00	SIDEWALK
80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY	90% FEDERAL 10% STATE	50% STATE 50% CITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				1000	Y031-1F	Y031-1F	Y030-1E	SFTY-1B
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	156	156				
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	1176	1176				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	67	67				
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	2	2				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	67	67				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1			1		
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	4		4			
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	58		58			
81021550	CONDUIT, AUGERED, 2" DIA., PVC	FOOT	246		26	220		
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP - TYPE USE) 3/4" DIA. POLYETHYLENE	FOOT	3450			3450		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3082		62	3020		
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	12			12		
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4			4		
82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4		4			
* 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP-240 VOLT	EACH	1			1		
83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	12			12		
83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	4			4		
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8"X6'	EACH	12			12		
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8"X8'	EACH	4			4		
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	64			64		
84200500	REMOVAL OF EXISTING LIGHTING UNIT - SALVAGE	EACH	2			2		
84200805	POLE FOUNDATION REMOVED, METAL	EACH	2			2		
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1	1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	36		36			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	104	56	48			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	847		847			

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION S(RS-5, TS-7).L
SANGAMON COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____

DATE: _____
FILE NAME: _____
PLOT SCALE: _____
REFERENCE: _____