

|                     |                |                  |              |           |
|---------------------|----------------|------------------|--------------|-----------|
| F.A.P. RTE.         | SECTION        | COUNTY           | TOTAL SHEETS | SHEET NO. |
| 67                  | S(RS-5,TS-7),L | SANGAMON         | 78           | 8         |
| STA.                |                | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS       | FED. AID PROJECT |              |           |

| PAVEMENT SCHEDULE   |                |                 |  |   |  |   |  |                              |                          |
|---|----------------|-----------------|--|---|--|---|--|------------------------------|--------------------------|
| LOCATION<br>STATION TO STATION                              | LENGTH<br>(FT) | WIDTH<br>(FT)   | HOT-MIX<br>ASPHALT SURF<br>REM BUTT - JOINT<br>(SQ YD)                       | PCC SURF<br>REM BUTT - JOINT<br>(SQ YD) | PCC SURF<br>REMOVAL<br>(VAR. DEPTH)<br>(SQ YD) | LEVEL BINDER<br>(MM)<br>N90 (1")<br>(TON) | HOT-MIX<br>ASPHALT SURF CSE<br>"D" N90 (1 1/2")<br>(TON) | BIT MAT<br>PRIME CT<br>(TON) | AGG<br>PRIME CT<br>(TON) |
| FAP 67 (IL 97/ JEFFERSON ST.)                               |                |                 |  |   |  |   |  |                              |                          |
| STA. 117+93.00 TO STA. 120+53.03 EAST BOUND                 | 260.03         | 25              | LIMITS OF CLASS C PATCHING ONLY FOR QUANTITIES SEE CLASS C PATCHING SCHEDULE |   |  |   |  |                              |                          |
| STA. 117+93.00 TO STA. 120+53.03 WEST BOUND                 | 260.03         | 49              | LIMITS OF CLASS C PATCHING ONLY FOR QUANTITIES SEE CLASS C PATCHING SCHEDULE |   |  |   |  |                              |                          |
| VETERANS PARKWAY OMISSION STA. 120+53.03 TO STA. 121+51.17  |                |                 |  |   |  |   |  |                              |                          |
| STA. 121+51.17 TO STA. 122+75.16 EAST BOUND                 | 123.99         | 25              | LIMITS OF CLASS C PATCHING ONLY FOR QUANTITIES SEE CLASS C PATCHING SCHEDULE |   |  |   |  |                              |                          |
| STA. 121+51.17 TO STA. 122+89.72 WEST BOUND                 | 138.55         | 37              | LIMITS OF CLASS C PATCHING ONLY FOR QUANTITIES SEE CLASS C PATCHING SCHEDULE |   |  |   |  |                              |                          |
| BRIDGE OMISSION STA. 122+75.16 TO STA. 126+44.10 EAST BOUND |                |                 |  |   |  |   |  |                              |                          |
| BRIDGE OMISSION STA. 122+89.72 TO STA. 126+60.84 WEST BOUND |                |                 |  |   |  |   |  |                              |                          |
| STA. 127+44.10 TO STA. 141+43.08 EAST BOUND                 | 1,398.98       | VAR. 27 - 41    | -  | 100                                     | 310.88   | 252.02                                    | 378.03   | 1.71                         | 9.00                     |
| STA. 127+60.84 TO STA. 141+43.08 WEST BOUND                 | 1,382.24       | VAR. 27 - 41    | -  | 102                                     | 307.16   | 285.35                                    | 428.00   | 1.94                         | 10.19                    |
| STA. 141+43.08 TO STA. 150+26.00                            | 882.92         | VAR. 74 - 71.63 | 203.57   | 437                                     | 620.28   | 387.87                                    | 598.94   | 2.71                         | 14.26                    |
| <b>TOTAL</b>  |                |                 | <b>204</b>   | <b>639</b>                              | <b>1239</b>                                    | <b>925.5</b>                              | <b>1405</b>  | <b>6.5</b>                   | <b>33.5</b>              |

NOTE: THOUGH CURB & GUTTER SECTION WIDTH IS FROM FACE TO FACE OF CURBS.

| BITUMINOUS SHOULDER SCHEDULE                                |                |   |   |   |                              |
|---|----------------|---|---|---|------------------------------|
| LOCATION<br>STATION TO STATION                              | LENGTH<br>(FT) | PROP. ASPHALT<br>SHOULDERS<br>WIDTH<br>(FT) | HOT-MIX<br>ASPHALT<br>SURF REM<br>(2")<br>(SQ YD) | HOT-MIX<br>ASPHALT<br>SHOULDERS,<br>(TON) | BIT MAT<br>PRIME CT<br>(TON) |
| FAP 67 (IL 97/ JEFFERSON ST.)                               |                |   |   |   |                              |
| LT. STA. 117+93.00 TO LT. STA. 120+53.03 EAST BOUND         | 260.03         | 10  | 337.77  | 37.83                                     | 0.13                         |
| LT. STA. 117+93.00 TO LT. STA. 120+53.03 WEST BOUND         | 260.03         | VARIES 10 TO 4                              | 253.29  | 28.37                                     | 0.10                         |
| VETERANS PARKWAY OMISSION STA. 120+53.03 TO STA. 121+51.17  |                |   |   |   |                              |
| RT. STA. 121+51.17 TO RT. STA. 122+75.16 EAST BOUND         | 123.99         | VARIES 5 TO 10                              | 198.50  | 22.23                                     | 0.07                         |
| LT. STA. 121+51.17 TO LT. STA. 122+82.44 WEST BOUND         | 138.55         | 10  | 266.90  | 29.89                                     | 0.10                         |
| BRIDGE OMISSION STA. 122+75.16 TO STA. 127+44.10 EAST BOUND |                |   |   |   |                              |
| BRIDGE OMISSION STA. 122+89.72 TO STA. 127+60.84 WEST BOUND |                |   |   |   |                              |
| RT. STA. 126+35.88 TO RT. STA. 127+94.10 EAST BOUND         | 158.22         | VAR. 10.58 TO 2                             | 114.04  | 12.77                                     | 0.04                         |
| LT. STA. 126+81.49 TO LT. STA. 128+17.00 WEST BOUND         | 135.51         | VAR. 10.58 TO 2                             | 94.71   | 10.61                                     | 0.04                         |
| RT. STA. 127+94.10 TO RT. STA. 141+43.08 EAST BOUND         | 1,348.98       | -   | -   | -   | -                            |
| LT. STA. 128+17.00 TO LT. STA. 141+43.08 WEST BOUND         | 1,326.08       | -   | -   | -   | -                            |
| STA. 141+43.08 TO STA. 150+26.00                            | 882.92         | -   | -   | -   | -                            |
| <b>TOTAL</b>  |                |   | <b>1265.5</b>                                     | <b>142</b>                                | <b>.50</b>                   |

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
**FAP 67 (IL 97/ JEFFERSON ST)**  
**SECTION S(RS-5,TS-7),L**  
**SANGAMON COUNTY**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_