

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	S(RS-5,TS-7),L	SANGAMON	78	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	SPACING	NUMBER OF LANE LINES	QUANTITY		
					TWO-WAY AMBER (EACH)	ONE-WAY AMBER (EACH)	ONE-WAY CRYSTAL (EACH)
FAP 67 (IL 97/ JEFFERSON ST.)							
WB STA. 130+94.00 TO STA. 132+00.00	LT. TURN LANE LINE (ONE-WAY CRYSTAL)	106.00	1 @ 40'	1	-	-	3
WB STA. 138+72.00 TO STA. 140+00.00	LT. TURN LANE LINE (ONE-WAY CRYSTAL)	128.00	1 @ 40'	1	-	-	4
WB STA. 143+70.00 TO STA. 145+14.00	LT. TURN LANE LINE (ONE-WAY CRYSTAL)	144.00	1 @ 40'	1	-	-	4
WB STA. 145+95.00 TO STA. 147+27.00	LT. TURN LANE LINE (ONE-WAY CRYSTAL)	132.00	1 @ 40'	1	-	-	4
STA. 143+66.00 TO STA. 145+13.00	PAINTED MEDIAN LINE (TWO-WAY AMBER)	147.00	1 @ 40'	2	10	-	-
STA 145+97.50 TO STA. 148+00.00	PAINTED MEDIAN LINE (TWO-WAY AMBER)	202.50	1 @ 40'	2	12	-	-
STA 148+00.00 TO STA. 150+26.00	BI-DIRECTIONAL LINE (TWO-WAY AMBER)	226.00	1 @ 40'	2	12	-	-
EB STA. 143+66.00 TO STA. 150+26.00	CENTER LINE SKIP-DASH (ONE-WAY CRYSTAL)	661.00	1 @ 80'	1	-	-	9
WB STA. 143+70.00 TO STA. 150+26.00	CENTER LINE SKIP-DASH (ONE-WAY CRYSTAL)	656.00	1 @ 80'	1	-	-	9
SUB-TOTAL					34	0	33
TOTAL					67		

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY
FAP 67 (IL 97/ JEFFERSON ST.)	67
TOTAL	
67	

PREFORMED PLASTIC PAVEMENT MARKING - LINE 5" TYPE B SCHEDULE

LOCATION STATION TO STATION	DESCRIPTION	LENGTH (FT)	NUMBER OF LANE LINES	QUANTITY (WHITE) (FT)	QUANTITY (YELLOW) (FT)
FAP 67 (IL 97/ JEFFERSON ST.)					
WB STA. 127+60.84 TO STA. 142+56.00	LANE LINE, SKIP-DASH	1495.16	1	373.8	-
WB STA. 143+70.00 TO STA. 150+26.00	LANE LINE, SKIP-DASH	656.00	1	164.0	-
EB STA. 127+44.10 TO STA. 142+70.50	LANE LINE, SKIP-DASH	1526.40	1	381.6	-
EB STA. 143+66.00 TO STA. 150+26.00	LANE LINE, SKIP-DASH	660.00	1	165.0	-
LT. STA 148+87.00 TO STA. 150+26.00	BI-DIRECTIONAL LANE LINE, SKIP-DASH	139.00	1	-	34.8
RT. STA 148+00.00 TO STA. 150+26.00	BI-DIRECTIONAL LANE LINE, SKIP-DASH	226.00	1	-	56.5
SUB-TOTAL				1084.4	91.3
TOTAL				1176	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B LETTERS AND SYMBOLS SCHEDULE

LOCATION STATION TO STATION	DESCRIPTION	QUANTITY (WHITE) (SQ FT)
FAP 67 (IL 97/ JEFFERSON ST.)		
WB STA. 131+19.00 TO STA. 131+95.00	LEFT TURN ARROWS (2 @ 76' CTS)	31.2
WB STA. 139+06.00 TO STA. 139+95.00	LEFT TURN ARROWS (2 @ 89' CTS)	31.2
EB STA. 141+83.00 TO STA. 142+44.00	LEFT TURN ARROWS (2 @ 61' CTS)	31.2
WB STA. 143+94.00 TO STA. 144+95.00	LEFT TURN ARROWS (2 @ 101' CTS)	31.2
WB STA. 146+23.00 TO STA. 147+22.00	LEFT TURN ARROWS (2 @ 99' CTS)	31.2
TOTAL		156

KEY: EB = EASTBOUND LANES
WB = WESTBOUND LANES

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FAP 67 (IL 97/ JEFFERSON ST)
SECTION S(RS-5, TS-7), L
SANGAMON COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE _____ DRAWN BY _____
CHECKED BY _____