

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6, TS	CHRISTIAN	47	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F
80% FED. / 20% STATE
HSIP
90% FED.
10% STATE

RURAL ROADWAY SEE NOTE 1
URBAN ROADWAY SEE NOTE 2
URBAN TRAFFIC SIGNALS

CONSTRUCTION CODE TYPE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A	1000-2A	Y031-1F
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.2	0.6	0.2
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.2	0.6	0.2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5672	536	5136	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	468		468	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	95817	7608.5	88208.5	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1933		1933	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1343		1343	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1089		1089	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	275		275	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	944	89	855	
72000100	SIGN PANEL - TYPE 1	SQ FT	46			46
72000200	SIGN PANEL - TYPE 2	SQ FT	56.5			56.5
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	105			105
73000100	WOOD SIGN SUPPORT	FOOT	30			30
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	95817	7608.5	88208.5	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1343		1343	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1089		1089	
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	468		468	
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1933		1933	
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	275		275	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	476	34	442	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8		8	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8		8	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	386	34	352	
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1			1
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1953			1953
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	13			13

NOTES:

1. STA. 0+00 TO STA. 26+80
2. STA. 26+80 TO STA. 68+12.31
 STA. EQ. 68+12.31BK=23+53.94AH
 STA. 23+53.94 TO STA. 112+99.14
 STA. EQ. 112+99.14BK=112+97.33AH
 STA. 112+97.33 TO STA. 188+05.74
 STA. EQ. 188+05.74BK=188+02.67AH
 STA. 188+02.67 TO STA. 227+41.20
 STA. EQ. 227+41.20BK=64+00AH
 STA. 64+00 TO STA. 64+20

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP ROUTE 714 (IL 48)
SECTION (135)RS-6, TS
CHRISTIAN COUNTY

SCALE: VERT. DATE: HORIZ. DRAWN BY: CHECKED BY: