

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6,TS	CHRISTIAN	47	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

HOT-MIX ASPHALT SHOULDERS SCHEDULE

LOCATION STATION TO STATION	WIDTH ( FT )	HOT-MIX ASPHALT THICKNESS ( IN )	HOT-MIX ASPHALT SURF REMOV ( 2" ) ( SQ YD )	HOT-MIX ASPHALT SHOULDERS ( TON )	BIT MAT PRIME CT ( TON )
FAP 714 ( ILL RTE 48 )					
IL 48 & SPRESSER ST. INTERSECTION NORTH CORNER	5	2	68.1	7.6	0.1
IL 48 & NOKOMIS RD. INTERSECTION STA. 75+81.00 RT. TO STA. 82+42.55 RT. SOUTH SIDE OF IL 48					
STA. 79+42.00 RT. TO STA. 81+40.00 RT.	4	2	160.4	18.0	0.1
SOUTH WEST CORNER ALONG NOKOMIS RD.	4	2	79.1	8.9	0.1
SOUTH EAST CORNER ALONG NOKOMIS RD.	4	2	88.9	10.0	0.1
STA. 81+42.00 RT. TO STA. 82+42.55 RT.	4	2	44.7	5.0	0.1
IL 48 & NOKOMIS RD. INTERSECTION STA. 79+14.00 LT. TO STA. 85+82.00 LT. NORTH SIDE OF IL 48					
STA. 79+14.00 LT. & ALONG NORTH WEST OF NOKOMIS RD.	4	2	95.6	10.7	0.1
NORTH EAST CORNER ALONG NOKOMIS RD.	4	2	59.6	6.7	0.1
STA. 82+20.00 LT. TO STA. 85+82.00 LT.	4	2	160.9	18.0	0.1
IL 48 & MACADAM DR. INTERSECTION					
SOUTH SIDE OF MACADAM DR.	3	2	84.7	9.5	0.1
NORTH SIDE OF MACADAM DR.	3.5	2	90.6	10.1	0.1
TOTALS			933	105	1.0

AGGREGATE SHOULDERS, TYPE B SCHEDULE

LOCATION STATION TO STATION	LENGTH ( FT )	WIDTH ( FT )	AGGREGATE SHOULDERS TYPE B ( Ton )
FAP 714 ( ILL RTE 48 )			
STA -0+20 TO STA 35+50.00	3,570.00	3	341.5
STA 35+50.00 TO STA. 37+67.98	217.98	3	20.9
STA. 37+67.98 LT. TO STA. 44+50.00 LT.	682.02	3	32.6
STA. 45+95.00 LT. TO STA. 50+59.00 LT.	464.00	3	22.2
STA. 37+67.98 RT. TO STA. 44+50.00 RT.	682.02	3	32.6
STA. 45+25.00 RT. TO STA. 50+59.00 RT.	534.00	3	25.5
STA. 50+59.00 TO STA 52+84.90	225.90	-	-
STA 52+84.90 TO STA 68+12.31	1,527.41	3	-
STA. E0. 68+12.31 BK. = 23+53.94 AH.			
STA 23+53.94 TO STA 73+86.00	5,032.06	3	481.4
STA. 73+86.00 LT. TO STA. 79+14.00 LT.	528.00	3	25.3
STA. 79+14.00 LT. TO STA. 82+20.00 LT.	SEE NOTE 1	3	17.5
STA. 82+20.00 LT. TO STA. 87+51.00 LT.	531.00	3	25.4
STA. 73+86.00 RT. TO STA. 79+42.00 RT.	556.00	3	26.6
STA. 79+42.00 RT. TO STA. 81+40.00 RT.	SEE NOTE 1	3	12.9
STA. 81+40.00 RT. TO STA. 87+51.00 RT.	611.00	3	29.2
STA. 87+51.00 TO STA. 91+30.00	379.00	3	36.3
STA 91+30.00 TO STA 112+99.14	2,169.14	3	207.5
STA. E0. 112+99.14 BK. = 112+97.33 AH.			
STA 112+97.33 TO STA 180+73.00	6,775.67	3	648.2
STA. 180+73.00 LT. TO STA. 187+13.00 LT.	640.00	3	30.6
STA. 180+73.00 RT. TO STA. 185+62.50 RT.	489.50	3	23.4
STA. E0. 188+05.74 BK. = 188+02.64 AH.			
STA. 190+04.00 LT. TO STA. 196+70.00 LT.	666.00	3	31.9
STA. 189+23.87 RT. TO STA. 196+70.00 RT.	746.13	3	35.7
STA 196+70.00 TO STA 208+79.00	1,209.00	3	115.7
STA. 208+79.00 LT. TO STA. 210+00.00 LT.	121.00	3	5.8
STA. 210+00.00 LT. TO STA. 212+30.00 LT.	SEE NOTE 1	3	15.5
STA. 212+30.00 LT. TO STA. 227+41.20 LT.	1,511.20	3	72.3
STA. 208+79.00 RT. TO STA. 227+41.20 RT.	1,862.20	3	89.1
STA. E0. 227+41.20 BK. = 64+00.00 AH.			
STA 64+00.00 TO STA 64+20.00	20.00	3	1.9
TOTAL			2408.0

PLOT DATE : \$DATE\$  
FILE NAME : \$FILEL\$  
PLOT SCALE : \$SCALE\$  
USER NAME : \$USER\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES  
FA ROUTE 714 (IL 48)  
SECTION (135)RS-6,TS  
CHRISTIAN COUNTY**

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY