

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6,TS	CHRISTIAN	47	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

THERMOPLASTIC PAVEMENT MARKING							
STATION TO STATION	LOCATION	DESCRIPTION	LINE 5"		LINE 8" FOOT	LINE 12" FOOT	
			WHITE (FOOT)	YELLOW (FOOT)			
IL48							
STA. 0+00.0 TO STA. 9+02.0	RT. & LT.	DOUBLE LINE	1804	1804			
STA. 9+02.0 TO STA. 33+39.0	RT. & LT.	SKIP-DASH	4874	609.3			
STA. 33+39.0 TO STA. 35+50.0	RT. & LT.	SINGLE LINE & SKIP DASH	422	263.8			
STA. 35+50.0 TO STA. 37+69.0	RT. & LT.	INTERSECTION	438	876		32.8	
STA. 37+69.0 TO STA. 44+49.0	RT. & LT.	INTERSECTION	1340.19	1422.59			
STA. 45+36.0 TO STA. 50+59.0	RT. & LT.	INTERSECTION	976.84	1047.65			
STA. 50+59.0 TO STA. 52+85.0	RT. & LT.	INTERSECTION	452	904		58.77	
STA. 52+85.0 TO STA. 56+05.0	RT. & LT.	SINGLE LINE & SKIP DASH	640	400			
STA. 56+05.0 TO STA. 61+24.0	RT. & LT.	SKIP-DASH	1038	129.8			
STA. 61+24.0 TO STA. 68+12.3	RT. & LT.	SINGLE LINE & SKIP DASH	1376.6	860.4			
STATION EQUATION STA. 68+12.3 BK TO STA. 23+53.9 AH							
STA. 23+53.9 TO STA. 24+74.0	RT. & LT.	SINGLE LINE & SKIP DASH	240	150.2			
STA. 24+74.0 TO STA. 45+54.0	RT. & LT.	DOUBLE LINE	4160	4160			
STA. 45+54.0 TO STA. 54+71.0	RT. & LT.	SINGLE LINE & SKIP DASH	1834	1146.3			
STA. 54+71.0 TO STA. 69+98.0	RT. & LT.	SKIP-DASH	3054	381.8			
STA. 69+98.0 TO STA. 72+91.0	RT. & LT.	SINGLE LINE & SKIP DASH	586	73.3			
STA. 72+91.0 TO STA. 73+88.0	RT. & LT.	INTERSECTION	194	388		17.7	
STA. 73+88.0 TO STA. 80+04.0	RT. & LT.	INTERSECTION	1152	1237.5			
STA. 79+68.0 TO STA. 80+47.0	RT.	INTERSECTION				79	
STA. 81+14.0 TO STA. 81+93.0	LT.	INTERSECTION				79	
STA. 81+61.0 TO STA. 87+50.0	RT. & LT.	INTERSECTION	1036.5	1183			
STA. 87+50.0 TO STA. 90+00.0	RT. & LT.	INTERSECTION	500	1000		46.8	
STA. 90+00.0 TO STA. 108+08.0	RT. & LT.	SINGLE LINE & SKIP DASH	3616	2260			
STA. 108+08.0 TO STA. 109+46.0	RT. & LT.	DOUBLE LINE	276	276			
STA. 109+46.0 TO STA. 112+99.1	RT. & LT.	SINGLE LINE & SKIP DASH	706.2	441.4			
STATION EQUATION STA. 112+99 BK TO STA. 112+97.3 AH							
STA. 112+97.3 TO STA. 119+53.0	RT. & LT.	SINGLE LINE & SKIP DASH	1311.4	819.6			
STA. 119+53.0 TO STA. 151+58.0	RT. & LT.	SKIP-DASH	6410.0	801.3			
STA. 151+58.0 TO STA. 154+03.0	RT. & LT.	SINGLE LINE & SKIP DASH	490	306.3			
STA. 154+03.0 TO STA. 180+94.0	RT. & LT.	DOUBLE LINE	5382	10764			
STA. 180+94.0 TO STA. 187+62.0	RT. & LT.	INTERSECTION	1000	2336		171.85	
STA. 187+38.0 TO STA. 187+91.0	LT.	INTERSECTION				53	
STATION EQUATION STA. 188+05.7 BK TO STA. 188+02.7 AH							
STA. 188+32.0 TO STA. 188+92.0	RT.	INTERSECTION				60	
STA. 188+62.0 TO STA. 190+26.0	RT. & LT.	INTERSECTION	105	164			
STA. 190+26.0 TO STA. 195+18.0	RT. & LT.	SKIP-DASH	984	1968		158.9	
STA. 195+18.0 TO STA. 227+41.0	RT. & LT.	SKIP-DASH	6446	805.8		156	
STATION EQUATION STA. 227+41.0 BK TO STA. 64+00.0 AH							
STA. 64+00.0 TO STA. 64+35.0	RT. & LT.	SKIP-DASH	70	8.8			

THERMOPLASTIC PAVEMENT MARKING							
STATION TO STATION	LOCATION	DESCRIPTION	LINE 5"		LINE 8" FOOT	LINE 12" FOOT	
			WHITE (FOOT)	YELLOW (FOOT)			
SPRESSER ST.							
STA. 9+87.5 TO STA. 9+60.5	RT.		113.57				
STA. 10+46.2 TO STA. 11+38.2	LT.		262.93	20			
NOKOMIS RD.							
STA. 38+25.4 TO STA. 40+00.0	RT.		504.26		183.23	141.31	
STA. 38+23.4 TO STA. 39+71.0	LT.		388.44		189.18	146.71	
LINCOLN TRAIL RD. AND E. MAIN CROSS ST.							
STA. 21+10.5 TO STA. 23+08.0	RT.		568.5	341.88	134.54	53.37	
STA. 20+67.6 TO STA. 18+93.0	LT.		584.45	318.3	112.02	78.89	
McADAM ST.							
STA. 0+37.1 TO STA. 2+11.0	LT.		489.91	320.91	296.78	182.08	
SUB TOTAL			55826.79	39989.93	1342.75	1089.18	
TOTAL			95817		1343	1089	

PAVEMENT PATCHING 13"				
LOCATION	TYPE			
	I (SQ YD)	II (SQ YD)	III (SQ YD)	IV (SQ YD)
IL48 (RURAL)				
SOUTH END OF JOB to STA. 26+80	50.00	68.00	16.00	-
RURAL SUB TOTALS	50.00	68.00	16.00	-
IL48 (URBAN)				
STA. 26+80 to SPRESSER ST.	50.00	45.33	16.00	
SPRESSER ST. to HOUSTON ST.		204.44	32.00	53.33
HOUSTON ST. to NOKOMIS RD.		53.33	16.00	-
NOKOMIS RD. to CHEROKEE ST.		21.33	32.00	-
CHEROKEE ST. to LINCOLN TRAIL		266.67	96.00	29.33
LINCOLN TRAIL to NORTH END OF JOB		129.33	16.00	-
URBAN SUB TOTALS	50.00	720.43	208.00	82.66
TOTALS	100	788	224	83

NOTE: TEMPORARY PAVEMENT MARKING QUANTITIES ARE THE SAME VALUES AS PERMANENT PAVEMENT MARKING QUANTITIES

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FA ROUTE 714 (IL 48)
SECTION (135)RS-6,TS
CHRISTIAN COUNTY

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY