

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662		MACOUPIN	68	2
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**GENERAL NOTES**

- 1 ALL ELEVATIONS SHOWN IN THE PLANS ARE U.S.G.S. MEAN SEA LEVEL DATUM.
- 2 ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS SHALL BE INTERRUPTED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS SHOWN IN THE PLANS.
- 3 THE THICKNESS OF BITUMINOUS MIXTURE SHOWN ON THE PLANS IS THE NORMAL THICKNESS. DEVIATIONS FROM THE NORMAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
- 4 SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET OR IN AN UNTILLABLE CONDITION. AREAS TO BE SEEDED SHALL BE DETERMINED BY THE ENGINEER.
- 5 EXISTING PAVEMENT DAMAGED DUE TO THE CONTRACTOR'S OPERATIONS, AND NOT OTHER WISE NECESSARY TO REPLACE, SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.
- 6 THE LOCATIONS OF THOSE BURIED AND ABOVE GROUND UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINE IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 800-892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCED NOTICE IS REQUIRED.
- 7 THE EXISTING ROAD SIGNS THAT INTERFERE WITH CONSTRUCTION SHALL BE RELOCATED AS DIRECTED BY THE ENGINEER. AFTER THE CONSTRUCTION IS COMPLETED, THE CONTRACTOR WILL REPLACE THE SIGNS AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 8 ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OUTSIDE THE LIMITS OF RIGHT-OF-WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARDS SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCLUDED IN TH COST OF EARTH EXCAVATION AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 9 WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER AND AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION IF THE ENGINEER DECIDES TO HAVE THE CONTRACTOR RESET THE MONUMENT, THIS WORK WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.
- 10 NO PASSING ZONES SHALL BE FIELD VERIFIED BY DAVE BERTETTO, DIST. 6, (217)785-0288, 14 DAYS PRIOR TO FINAL PAVEMENT MARKINGS.
- 11 THE FOLLOWING APPLICATION RATES WERE USED FOR QUANTITY CALCULATIONS.

- BITUMINOUS SURFACE COURSE, \_\_\_\_\_ 0.056 TON / SQ YD • IN
- AGGREGATE SHOULDERS TYPE A \_\_\_\_\_ 2.05 TON / CU YD
- BITUMINOUS MATERIAL (PRIME COAT) \_\_\_\_\_ 0.00038 TON / SQ YD
- NITROGEN \_\_\_\_\_ 90 LBS / ACRE
- PHOSPHOROUS \_\_\_\_\_ 90 LBS / ACRE
- POTASSIUM \_\_\_\_\_ 90 LBS / ACRE
- LIMESTONE \_\_\_\_\_ 2 TON / ACRE
- MULCH \_\_\_\_\_ 2 TON / ACRE
- TEMPORARY EROSION CONTROL SEEDING \_\_\_\_\_ 100 LB / ACRE
- RIPRAP \_\_\_\_\_ 1.50 TON / CU YD
- AGGREGATE SHOULDERS TYPE B \_\_\_\_\_ 1.89 TON / CU YD

12 THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT.

MIXTURE USE	Surface 40603310	Level Binder 40600625	Binder 40603080	Incidental Surface 40800050	Base Course Widening 10" 35600716	Shoulders 48203100
AC/PG	PG 64-22	PG 64-22	PG 64-22	PG 64-22	PG 64-22	PG 58-22
DESIGN AIR VOIDS	4.0 @ N Design = 50	4.0 @ N Design = 50	4.0 @ N design = 50	4.0 @ N design = 50	4.0 @ N design = 50	2.0 @ N design = 30
MIXTURE COMPOSITION (GRADATION MIXTURE)	IL 9.5 OR 12.5	IL 9.5	IL 19.0	IL 9.5 or 12.5	IL 19.0	BAM
FRICITION AGGREGATE	Mix "C"	N/A	N/A	Mix "C"	N/A	N/A

**COMMITMENTS**

- THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES & PLANS CONCERNING ANY MAJOR PLAN CHANGES TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS.

*GEN. NOTES (cont.)*

13. INSTALLATION OF THE PIPE CULVERT AT STA. 450+63.40 SHALL BE COMPLETED BEFORE STANDARD 701321 CAN BE INSTALLED.

14. DRAINAGE AGGREGATE AND POROUS GRANULAR EMBANKMENT SHALL BE CA-07 MATERIAL.

15. TOPSOIL SHALL BE IN ACCORDANCE WITH ARTICLE 211 OF THE STANDARD SPECIFICATIONS WITH A MINIMUM DEPTH OF 4 INCHES. THE QUANTITY OF TOPSOIL HAS BEEN INCLUDED IN FURNISHED EXCAVATION AND WILL NOT BE PAID FOR SEPARATELY.

EXAMINED Dec 14 2006

*[Signature]*

PROGRAM IMPLEMENTATION ENGINEER

---

DISTRICT SIX

---

EXAMINED December 14 2006

*[Signature]*

OPERATIONS ENGINEER

---

EXAMINED December 15 2006

*[Signature]*

PROGRAM DEVELOPMENT ENGINEER

Rev. 4-16-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES & COMMITMENTS**

REVISIONS	
NAME	DATE

SCALE: VERT. \_\_\_\_\_ HORIZ. \_\_\_\_\_ DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_ CHECKED BY \_\_\_\_\_

c:\projects\652685\cover.dgn  
 12/13/2006  
 REF:01