

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	MACOUPIN	68	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

(IV, T) B-2

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
			80% FED. 20% STATE	RURAL ROADWAY 1000 80% FED 20% STATE	IL 4 BRIDGE X081-2A 80% FED 20% STATE
PAY CODE NUMBER	PAY ITEM DESCRIPTION				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2	-
40600300	AGGREGATE (PRIME COAT)	TON	12	12	-
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	135	135	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	375	375	-
40600990	TEMPORARY RAMP	SQ YD	99	99	-
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	970	970	-
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	215	215	-
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	25	25	-
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	245	245	-
44000100	PAVEMENT REMOVAL	SQ YD	130	130	-
44004250	PAVED SHOULDER REMOVAL	SQ YD	20	20	-
44200108	PAVEMENT PATCHING, TYPE II, 9 INCH	SQ YD	18	18	-
48101200	AGGREGATE SHOULDERS, TYPE B	TON	350	350	-
48203100	HOT-MIX ASPHALT SHOULDERS	TON	155	155	-
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	-	1
50105200	REMOVE EXISTING CULVERTS	EACH	1	1	-
50200100	STRUCTURE EXCAVATION	CU YD	260	-	260
50300225	CONCRETE STRUCTURES	CU YD	52.3	-	52.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	144.5	-	144.5
50300260	BRIDGE DECK GROOVING	SQ YD	580	245	335

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

SCALE: VERT.
DATE

DRAWN BY
CHECKED BY

Rev.

PLOT DATE
PLOT SCALE
USER NAME