

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	MACOUPIN	68	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

(V,T) B-2

SUMMARY OF QUANTITIES		UNITS	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
PAY CODE NUMBER	PAY ITEM DESCRIPTION		80% FED. 20% STATE	RURAL ROADWAY 1000 80% FED 20% STATE	IL 4 BRIDGE X081-2A 80% FED 20% STATE
50300300	PROTECTIVE COAT	SO YD	431	-	431
50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.	FOOT	524.5	-	524.5
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	32,120	-	32,120
50800515	BAR SPLICERS	EACH	355	-	355
51201105	FURNISHING METAL SHELL PILES 14"	FOOT	931	-	931
51202305	DRIVING PILES	FOOT	931	-	931
51203200	TEST PILE METAL SHELLS	EACH	2	-	2
51500100	NAME PLATES	EACH	1	-	1
542A0229	PIPE CULVERT, CLASS A, TYPE 1 24"	FOOT	53	53	-
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	-
54215547	METAL END SECTIONS 12"	EACH	2	2	-
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	113	-	113
60103500	PIPE DRAINS, CORRUGATED STEEL 12"	FOOT	20	20	-
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	248	-	248
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	2	2	-
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	950	950	-
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	-
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	4	4	-
63200310	GUARDRAIL REMOVAL	FOOT	436	436	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	-

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
DATE

DRAWN BY
CHECKED BY