

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES, & SIGNATURES
3	SUMMARY OF QUANTITIES
4	EXISTING PLAN & ELEVATION VIEWS
5	CONCRETE REMOVAL DETAILS
6	PROPOSED PARAPET DETAILS
7	REINFORCEMENT DETAILS
8	BAR DRILLING LOCATION DETAILS
9	WINGWALL & TAPER CONCRETE DETAILS
10	WINGWALL & TAPER REINFORCEMENT DETAILS




STANDARDS

701101-01
701106-01
701400-02
701402-05
701406-04
702001-06
704001-03

GENERAL NOTES:

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE FOR THE WORK.

EXISTING VERTICAL REINFORCEMENT EXTENDING INTO THE REMOVAL AREA SHALL BE CLEANED, STRAIGHTENED, AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY VERTICAL REINFORCEMENT BARS THAT ARE DAMAGED DURING CONCRETE REMOVAL SHALL BE REPLACED WITH AN APPROVED BAR SPLICER OR ANCHORAGE SYSTEM. COST SHALL BE INCLUDED WITH CONCRETE REMOVAL.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED	January 8 20 07
 ENGINEER OF OPERATIONS	
EXAMINED	Jan 9 20 07
 ENGINEER OF PROGRAM IMPLEMENTATION	
EXAMINED	Jan 9 20 07
 ENGINEER OF PROGRAM DEVELOPMENT	

CONTRACT 72A87
INDEX OF SHEETS,
GENERAL NOTES,
& SIGNATURES