



NOTES:

CARE SHALL BE TAKEN AT THE REMOVAL POINT WHERE THE PARAPET MEETS THE EXISTING MICROSILICA OVERLAY. THE ENGINEER MAY ELECT TO REQUIRE A SAW CUT AND/OR REMOVAL BY HAND AT THIS LOCATION IN ORDER TO ENSURE PROTECTION OF THE MICROSILICA BRIDGE DECK. AN APPROVED SEALANT AS DETAILED IN THE SPECIAL PROVISIONS SHALL BE APPLIED IN THIS AREA AFTER RECONSTRUCTION IS COMPLETE. THE CONTRACTOR SHALL INCLUDE THE PRICE OF ALL WORK DESCRIBED ABOVE IN THE BID PRICE FOR CONCRETE SUPERSTRUCTURE.

THE PROTECTIVE SHIELD SHALL EXTEND INWARD TO THE WEB OF THE FIRST BEAM AND SHALL SERVE AS A BOTTOM FORM FOR ANY STRUCTURAL REPAIR OF CONCRETE FOR THE DECK THAT BECOMES NECESSARY DUE TO SPALLING CONCRETE DURING REMOVAL.

CONTRACT 72A87
CONCRETE REMOVAL
DETAILS
(NOT TO SCALE)