

CONTRACT # 72A98

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	SANGAMON	14	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D6 DIRKSEN/CLEARLAKE RES 2007
 ** FAP 67 - CLEAR LAKE
 FAP 75, 668 - DIRKSEN

SUMMARY OF QUANTITIES			URBAN
CODE NO	PAY ITEM	UNIT	100% STATE 1000 QUANTITY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8.7
40600300	AGGREGATE (PRIME COAT)	TON	30.4
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	378
40600990	TEMPORARY RAMP	SO YD	175
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1669
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	32
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	15178
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SO YD	75
60255500	MANHOLES TO BE ADJUSTED	EACH	9
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3
67100100	MOBILIZATION	L SUM	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1050
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	175
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	6440
* 78000400	THERMOPLASTIC PAVMENT MARKING - LINE 6"	FOOT	774
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2754
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	603
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SO FT	280.8
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	216
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	103
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	103

* SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 SECTION: D6 DIRKSEN/CLEARLAKE
 RES 2007
 SANGAMON COUNTY