

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO	82-34VB-38-5	SI, CL&B	99	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90%FED/10%ST ROADWAY JO00	90%FED/10%ST SN 082-0141 ROADWAY A X531-2A	90%FED/10%ST SN 082-0146 RAMP T X531-2A
<del>44000915</del>	<del>HOT-MIX ASPHALT SURFACE REMOVAL (DECK)</del>	<del>SQ YD</del>	<del>9629</del>		8227	1402
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	141	141		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	16	16		
<del>44000910</del>	<del>BITUMINOUS CONCRETE REMOVAL (DECK)</del>	<del>SQ YD</del>	<del>9629</del>		<del>8227</del>	<del>1402</del>
44002400	CURB REMOVAL (SPECIAL)	FOOT	15		7.5	7.5
50102400	CONCRETE REMOVAL	CU YD	1413		1126	287
50157300	PROTECTIVE SHIELD	SQ YD	2894		2574	320
50300225	CONCRETE STRUCTURES	CU YD	10		10	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1286		1026	260
50300260	BRIDGE DECK GROOVING	SQ YD	10557		8969	1588
50300300	PROTECTIVE COAT	SQ YD	14897		12372	2525
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	15		15	
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1		1	
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1			1
50606401	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1		1	
50606402	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1			1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	203080		165240	37840
50800515	BAR SPLICERS	EACH	533		533	
52000208	FINGER PLATE EXPANSION JOINT, 3"	FOOT	78		78	
52000216	FINGER PLATE EXPANSION JOINT, 5"	FOOT	33		33	
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	26			26
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	129		129	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	5		5	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24		
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	24	24		
67100100	MOBILIZATION	L SUM	1	1		
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	4	4		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90%FED/10%ST ROADWAY JO00	90%FED/10%ST SN 082-0141 ROADWAY A X531-2A	90%FED/10%ST SN 082-0146 RAMP T X531-2A
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8950	8950		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2200	2200		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4100	4100		
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1100	1100		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	3400	3400		
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	7100	7100		
*78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	2100	2100		
*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	1300	1300		
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	40	40		
*78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	100	100		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1750	1750		
X0320887	POLYMER CONCRETE	CU FT	42		32	10
X0321744	SILICONE JOINT SEALER, 2"	FOOT	171		171	
X0321781	MECHANICAL SPLICE	EACH	72		72	
X0322556	STIFFENER INTERSECTION MODIFICATION	EACH	1176		896	280
X0322559	BOLT REPLACEMENT	EACH	201		201	
X0322560	CRACK EXTENSION MODIFICATION	EACH	25		20	5

\* SPECIALTY ITEMS

Rex