

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			UNIFORM TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE ROADWAY 1000-2A	80% FEDERAL 20% STATE FRONTAGE ROAD 1000-2A	80% FEDERAL 20% STATE SIGNING Y002-1C	100% STATE SIGNING Y002-1C
M2510120	MULCH, METHOD 2	M TON	96.1	90.1	6		
M2510630	EROSION CONTROL BLANKET	SQ M	4692		4692		
M2800200	EARTH EXCAVATION FOR EROSION CONTROL	CU M	198	169	29		
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	3364	3156	208		
M2800400	PERIMETER EROSION BARRIER	METER	4723	4349	374		
M2801000	AGGREGATE (EROSION CONTROL)	M TON	55	52	3		
M2810105	STONE RIPRAP, CLASS A3	SQ M	322		322		
M2810107	STONE RIPRAP, CLASS A4	SQ M	13		13		
M2820200	FILTER FABRIC	SQ M	13		13		
M3021500	LIME	M TON	2625	2449	176		
M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C	M TON	19065	19065			
M3510200	AGGREGATE BASE COURSE, TYPE A 200MM	SQ M	1003		1003		
M4030200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	1.7		1.7		
M4030400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	M TON	5.1		5.1		
M4030500	COVER COAT AGGREGATE	M TON	2.6		2.6		
M4030600	SEAL COAT AGGREGATE	M TON	1.3		1.3		
M4060895	CONSTRUCTING TEST STRIP	EACH	2	2			
M4075190	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 190MM	SQ M	6193		6193		
M4075280	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 280MM	SQ M	11592	11592			
M4075350	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 350MM	SQ M	7591	7591			
M4075380	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 380MM	SQ M	50081	50081			
M4205000	BRIDGE APPROACH PAVEMENT	SQ M	926	926			
M4205200	PROTECTIVE COAT	SQ M	926	926			
M4810150	AGGREGATE SHOULDERS, TYPE A 150MM	SQ M	2228		2228		
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	10152	10152			
M4820590	HOT-MIX ASPHALT SHOULDERS, 190MM	SQ M	2032		2032		
M4820600	HOT-MIX ASPHALT SHOULDERS, 200MM	SQ M	42809	42809			
M5080105	REINFORCEMENT BARS	KG	475.6			475.6	
M542E012	END SECTIONS 300MM	EACH	1	1			
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	6		6		
M542E144	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 900MM	EACH	2		2		

4402154
3/22/2007
c:\projects\m037921\plan\sumquan.dgn
REF-
REF-