

SIGNING PLANS

INDEX OF SHEETS

- 1 INDEX OF SHEETS, BILL OF MATERIAL
- 2 GENERAL NOTES
- 3-4 SCHEDULES
- 5-10 OVERHEAD SIGN STRUCTURE PLANS
- 11-14 BRIDGE MOUNTED SIGN STRUCTURE PLANS
- 15-16 BREAKAWAY WIDE FLANGE PLANS
- 17-19 TRAFFIC CONTROL PLAN AND PROTECTION SPECIAL
- 20 IMPACT ATTENUATOR DETAILS
- 21-25 SIGN PANEL DETAILS
- 26-34 OVERHEAD SIGN STRUCTURE CROSS SECTIONS
- 35-40 BREAKAWAY WIDE FLANGE CROSS SECTIONS

BILL OF MATERIAL

FURNISHED EXCAVATION	CU M	702
REINFORCEMENT BARS	KG	475.6
SIGN PANEL - TYPE 1	SQ M	7.1
SIGN PANEL - TYPE 2	SQ M	12.1
SIGN PANEL - TYPE 3	SQ M	193.9
STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	KG	2462
WOOD SIGN SUPPORT	M	133.5
OVERHEAD SIGN STRUCTURE - SPAN (SPECIAL)	M	60.5
OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	M	8.5
OVERHEAD SIGN STRUCTURE WALKWAY	M	35.7
CONCRETE FOUNDATIONS	CU M	9.4
DRILLED SHAFT CONCRETE FOUNDATIONS	CU M	25.2
IMPACT ATTENUATORS (NON-REDIRECTIVE, TEST LEVEL 3	EACH	9
TRAFFIC CONTROL AND PROTECTION - SPECIAL	L SUM	1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		INDEX OF SHEETS BILL OF MATERIALS FAP 310 SECTIONS 60-14-2 & 60-14-2B MADISON COUNTY

SCALE: VERT. DATE
 HORIZ. DRAWN BY
 CHECKED BY

PLOT DATE = #DAYS*
 FILE NAME = #FILE*
 PLOT SCALE = #SCALE*
 USER NAME = #USER*