

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	1000 90% FED 10% STATE	1000 90% FED 10% STATE	Y031-1F 90% FED 5% STATE 5% COUNTY
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	10			10
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	30			30
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	8			8
81018400	CONDUIT PUSHED, 1 1/2" DIA., GALVANIZED STEEL	FOOT	46			46
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	80			80
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	55			55
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	122			122
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4			4
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1			1
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	243			243
81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	36			36
85000500	MAINTENANCE OF EXISTING FLASHING BEACON INSTALLATION	EACH	1			1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1
* 85800300	FLASHER CONTROLLER, WITHOUT CABINET	EACH	1			1
87301115	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 2C	FOOT	2115			2115
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3100			3100
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	920			920
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3200			3200
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	30			30
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	3			3
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1			1
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3			3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	46			46
87900200	DRILL EXISTING HANDHOLE	EACH	5			5
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1

\* SPECIALTY ITEMS

Rev. 4-16-07