CONTRACT NO. 76994

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	*	MADISON	42	10

* 125RS-1, 125I-2TS-2

HMA BASE COURSE WIDENING, 11"

LOCATION		HMA BASE COURSE WIDENING, 11"
STA.	STA.	(SQ YD)
220+75 LT	224+00 LT	140
224+00 LT	224+88 LT	45
TOTAL		185

SUB-BASE GRANULAR MATERIAL, TYPE C

LOCATION		SUB-BASE GRAN. MAT., TYPE C
STA.	STA.	(TONS)
220+75 LT	224+90 LT	320

AGGREGATE WEDGE SHOULDER, TYPE B

LOCATION		AGG WEDGE SHOULDER, TYPE B
STA.	STA.	(TON)
220+75 RT	224+50 RT	32
224+50	230+00	100
230+00	235+00	85
235+00	236+66.18	30
TOTAL		247

HMA SURFACE REMOVAL, 3/4"

LOCATION		HMA SURFACE REMOVAL, 3/4"
STA.	STA.	(SQ YD)
204+75	220+75	4,560
SMART SUBTOTAL		4,560
220+75	224+00	1,060
224+00	230+00	4,215
230+00	235+00	2,390
235+00	236+26.68	595
3R SUBTOTAL		8,260
TOTAL		12,820

AGGREGATE SHOULDERS, TYPE A 6"

LOCATION		AGG. SHOULDERS, TYPE A 6"
STA.	STA.	(SQ YD)
220+75 LT	224+50 LT	135
TOTAL		135

HMA SHOULDERS, 8'

LOCATION		HMA SHOULDERS, 8"
STA.	STA.	(SQ YD)
220+75 LT	224+88 LT	156
TOTAL		156

HMA SHOULDERS (TON)

LOCATION		HMA SHOULDERS
STA.	STA.	(TON)
220+75 RT	224+80 RT	18.7
224+80	230+00	85.1
230+00	235+00	63.3
235+00	236+66.38	39.2
TOTAL		206.3

SEEDING, CLASS 2

LOCATION		SEEDING, CLASS 2	NITROGEN FERT. NUTR.	PHOSPORUS FERT. NUTR.	POTASSIUM FERT. NUTR.
STA.	STA.	(ACRE)	(LB)	(LB)	(LB)
220+75 RT	224+95	0.70	63	63	63
TOTAL		0.70	63	63	63

PLOT DATE = 1/23/2007
FILE NAME = c:\projects\ed83486\plan\plnd83486a.dgn
PLOT SCALE = 50.2000 ' / IN.
REFERENCE = REF

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 789
SECTION 125RS-1, 125I-2TS-2
MADISON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY