

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	*	MADISON	42	12

* 125RS-1, 1251-2TS-2

PAVEMENT MARKING SCHEDULE

LOCATION		THERMO PAVEMENT MARKING - 4"				THERMO PAVEMENT MARKING - 12"			THERMO P.M. 8"	THERMO P.M. 24"	THERMO. P.M. - LETTERS AND SYMBOLS
STA	STA	WHITE EDGE LINE (FOOT)	WHITE SKIP-DASH (FOOT)	DOUBLE YELLOW LINE (FOOT)	WHITE LANE LINE (FOOT)	YELLOW DIAGONALS (FOOT)	WHITE STOP BAR (FOOT)	YELLOW MEDIAN (FOOT)	WHITE (FOOT)	WHITE STOP BAR (FOOT)	(SQ FT)
SMART											
204+35	206+00	340.0		680.0		88.0					
206+00	212+00	1,200.0		1,500.0		35.0					
212+00	218+00	1,200.0		1,200.0							
218+00	220+75	550.0		550.0							
SUBTOTAL		3,290.0		3,930.0		123.0					
SMART TOTAL				7,220.0		123.0			0.0		0.0
3R											
220+75	224+00	650.0	42.0	1,266.0		80.0					
224+00	230+00	1,082.0	74.0	1,490.0	505.0	40.0	24.0	556.0	405.0	175.0	135.2
230+00	235+00	1,010.0	36.0	1,812.0	85.0	93.0					15.6
235+00	236+66.68	334.0		334.0							
SUBTOTAL		3,076.0	152.0	4,902.0	590.0	213.0	24.0	556.0	405.0	175.0	150.8
3R SUBTOTAL				8,720.0		793.0			405.0	175.0	150.8
GRAND TOTAL				15,940.0		916.0			405.0	175.0	150.8

REMOVE SIGN PANEL ASSEMBLY

LOCATION	REMOVE SIGN PANEL - ASSEMBLY - TYPE A (EACH)
SMART	
NPZ STA. 214+00 RT	1
NPZ STA. 215+00 LT	1
SMART SUBTOTAL	
	2
3R	
4 STOP SIGNS AT INTERSECTION	4
TOTAL	
	6

REMOVE SIGN PANEL - TYPE 1

LOCATION	REMOVE SIGN PANEL - TYPE 1 (SQ FT)
SMART	
NPZ STA. 214+00 RT	5.6
NPZ STA. 215+00 LT	5.6
SMART SUBTOTAL	
	11.2
3R	
4 STOP SIGNS AT INTERSECTION	25.0
TOTAL	
	36.2

SHORT-TERM AND WORK ZONE PAVEMENT MARKING

LOCATION		SHORT -TERM PAVEMENT MARKING (FOOT)	WORK ZONE P.M. REMOVAL (SQ FT)
STA.	STA.		
SMART SECTION			
204+35	206+00	120	13.3
206+00	212+00	360	40.0
212+00	218+00	360	40.0
218+00	220+75	192	21.3
SMART SUBTOTAL		1,032	114.6
3R SECTION			
220+75	224+00	512	56.8
224+00	230+00	6,500	721.6
230+00	235+00	360	40.0
235+00	236+66.68	72	8.0
3R SUBTOTAL		7,444	826.4
TOTAL		8,476	941.0

A QUANTITY OF SHORT-TERM PAVEMENT MARKING HAS BEEN ADDED FOR TURN LANE ARROWS AND STOP BARS.

STRIP REFLECTIVE CRACK CONTROL TREATMENT

LOCATION		STRIP RELECTIVE CRACK CONTROL TREATMENT (FOOT)
STA.	STA.	
220+75 LT	224+48 LT	413
TOTAL		413

TEMPORARY RAMP

LOCATION	TEMPORARY RAMP (SQ YD)
SMART	
STA. 204+35	32
SUBTOTAL	
	32
3R	
WANDA RD	32
MORELAND RD	38
STA. 236+66.68	22
SUBTOTAL	
	92
TOTAL	
	124

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES FAP ROUTE 789 SECTION 125RS-1, 1251-2TS-2 MADISON COUNTY SCALE: VERT. _____ HORIZ. _____ DATE _____ DRAWN BY _____ CHECKED BY _____