

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
793	T-2-I	MADISON	41	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A 90% FED. 10% STATE	-----	-----
20200100	EARTH EXCAVATION	CU YD	1765	1765		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2754	2754		
25000115	SEEDING, CLASS 1B	ACRE	0.9	0.9		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	80	80		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	80	80		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	80	80		
25100115	MULCH, METHOD 2	ACRE	0.9	0.9		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	180	180		
28000300	TEMPORARY DITCH CHECKS	EACH	16	16		
28100105	STONE RIPRAP, CLASS A3	SQ YD	70	70		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	140	140		
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	3059	3059		
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	305	305		
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	10	10		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	110	110		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.9	3.9		
40600300	AGGREGATE (PRIME COAT)	TON	25	25		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	16	16		
40600990	TEMPORARY RAMP	SQ YD	13.4	13.4		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1260	1260		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	375	375		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	70	70		
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	180	180		
42001200	PAVEMENT FABRIC	SQ YD	180	180		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2500	2500		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	460	460		
44004250	PAVED SHOULDER REMOVAL	SQ YD	625	625		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3740	3740		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	280	280		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	610	610		
50105220	PIPE CULVERT REMOVAL	FOOT	61	61		
54200643	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	102	102		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-2A 90% FED. 10% STATE	-----	-----
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	12		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1240	1240		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	26	26		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8760	8760		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	355	355		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4297	4297		
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2		
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	30.5	30.5		
73000100	WOOD SIGN SUPPORT	FOOT	64	64		
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	26	26		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	8760	8760		
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	355	355		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	114	114		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	34	34		
Z0055400	RUMBLE STRIP	FOOT	1868	1868		

* ←

*SPECIALTY ITEMS

PLOT DATE = #DATE*
 PLOT SCALE = #SCALE*
 REFERENCE = #REF*