CONTRACT NO. 76A84

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60(1,2,3) I	MADISON	10	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: J000 90% FED. 10% STATE		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7		
40600300	AGGREGATE (PRIME COAT)	TON	36	36		
42001200	PAVEMENT FABRIC	SQ YD	708	708		
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	1650	1650		
44201011	CLASS B PATCHES, TYPE III, 13 INCH	SQ YD	586	586		
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	123	123		
44213200	SAW CUTS	FOOT	10265	10265		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	24	24		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8	8		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4261	4261		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21308	21308		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	722	722		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1406	1406		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21308	21308		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	722	722		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	110	110		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	110	110		
X4421000	PARTIAL DEPTH PATCHING	TON	2654	2654		
X4422025	PARTIAL DEPTH REMOVAL 2"	SQ YD	23659	23659		
Z0017202	DOWEL BARS 1 1/2"	EACH	3726	3726		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		

*SPECIALTY ITEMS

PLOT DATE = 2/24/2007
FILE NAME = c:\projects\c46587\plan\pln46587sum.dgn
PLOT SCALE = 100.0024 ' / IN.
REFERENCE = 44659