

SUMMARY OF QUANTITIES

F.A.U. ROUTE	CONTRACT NO.	COUNTY	TOTAL SHEETS
3877	83622	KANE	42
SECTION			3
97-0084-00-CH			
SUMMARY OF QUANTITIES			
F.H.W.A. REG.5 ILLINOIS PROJECT CMM-7003 16			

CODE NO	ITEM	UNIT	TOTAL QUANTITY	Y008-1A ROADWAY	Y031-1F SIGNALS	Y031-3D NON-PART.
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	38	38		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	24		
20101100	TREE TRUNK PROTECTION	EACH	18	18		
20101200	TREE ROOT PRUNING	EACH	7	7		
20200100	EARTH EXCAVATION	CU YD	1,525	1,525		
20200200	ROCK EXCAVATION	CU YD	10	10		
20800150	TRENCH BACKFILL	CU YD	108	108		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,865	1,865		
21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	30	30		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24	24		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24	24		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24	24		
* 25200110	SODDING, SALT TOLERANT	SQ YD	1,865	1,865		
* 25200200	SUPPLEMENTAL WATERING	UNIT	56	56		
28000510	INLET FILTERS	EACH	16	16		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3,030	3,030		
35401100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING (VARIABLE DEPTH)	SQ YD	1,054	1,054		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	943	943		
40800982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	676	676		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	537	537		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20		
42001300	PROTECTIVE COAT	SQ YD	1,735	1,735		
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	360	360		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,435	3,435		
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	935	935		
42400800	DETECTABLE WARNINGS	SQ FT	320	320		
44000100	PAVEMENT REMOVAL	SQ YD	907	907		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,848	1,848		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	353	353		
44000300	CURB REMOVAL	FOOT	1,416	1,416		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	696	696		
44000600	SIDEWALK REMOVAL	SQ FT	5,250	5,250		
44201398	CLASS C PATCHES, TYPE I, 14 INCH	SQ YD	25	25		
44201407	CLASS C PATCHES, TYPE III, 14 INCH	SQ YD	58	58		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,230	2,230		
550A2300	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 1 8"	FOOT	235	235		
550A2310	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 1 10"	FOOT	14	14		
550A2320	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 1 12"	FOOT	136	136		
550A2520	STORM SEWERS, RUBBER GASKET CLASS A, TYPE 2 12"	FOOT	74	74		

CODE NO	ITEM	UNIT	TOTAL QUANTITY	Y008-1A ROADWAY	Y031-1F SIGNALS	Y031-3D NON-PART.
55100300	STORM SEWER REMOVAL 8"	FOOT	5	5		
55100500	STORM SEWER REMOVAL 12"	FOOT	14	14		
55100700	STORM SEWER REMOVAL 15"	FOOT	18	18		
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	140	140		
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	60	60		
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	2	2		
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	6	6		
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	2	2		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	11	11		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	2	2		
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1		
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	5		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1		
60500040	REMOVING MANHOLES	EACH	1	1		
60500050	REMOVING CATCH BASINS	EACH	10	10		
60600605	CONCRETE CURB, TYPE B	FOOT	117	117		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	617	617		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,273	1,273		
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	590	590		
* 66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	1	1		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	288	288		
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2		
* 66901000	BACKFILL PLUGS	CU YD	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
* 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	600	600		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2,400	2,400		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	400	400		
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	210	210		
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	200	200		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	12	12		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	55	55		
* 72900200	METAL POST - TYPE B	FOOT	28	28		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ F	338	338		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,950	2,950		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,454	1,454		

* SPECIALTY ITEM